# **SOLICITATION FOR OFFERS**

THE GENERAL SERVICES ADMINISTRATION

FOR

Office of National Drug Control Policy

IN

Washington DC

TAWANDA BEVERLY
CONTRACTING OFFICER

MATT WITLIN BROKER REPRESENTATIVE PHONE: 202.639.4542 FAX: 202.654.7248

The information collection requirements contained in this Solicitation/Contract, that are not required by the regulation, have been approved by the Office of Management and Budget pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

SFO NO.06-031

09/07/06

INITIALS:

I ESSOR

GOVT

# TABLE OF CONTENTS

1. 0	SUMMARY	5
1.1	AMOUNT AND TYPE OF SPACE (SEP 2000)	5
1.2	AREA OF CONSIDERATION (jul 2005)	
1.3	LOCATION: CITY CENTER (NCR VaRIATION (JUNE 2006)	5
1.4	UNIQUE REQUIREMENTS.	5
1.5	LEASE TERM (SEP 2000)	
1.6	OFFER DUE DATE	
	OCCUPANOV DATE (OFFI 2000)	
1.7	OCCUPANCY DATE (SEP 2000)	
1.8	HOW TO OFFER (NCR VARIATION (JUL 2006))	ە
1.9	BUILDING SHELL REQUIREMENTS (NCR Variation (AUG 2002))	8
1.10	TENANT IMPROVEMENTS (SEP 2000)	9
1.11	TENANT IMPROVEMENT RENTAL ADJUSTMENT (SEP 2000)	9
1.12	PLANS WITH OFFER (SEP 2000)	10
1.13	BROKER COMMISSION AND COMMISSION CREDIT (JUL 2006)	
1.14	NEGOTIATIONS (May 2005)	10
1.15	PRICE EVALUATÌON (PREŚENT VALUE) (NCR VARIATION (MAY 2005))	
1.16	AWARD (JAN 1997)	11
1.17	LABOR STANDARDS (aug 2003)	12
1.18	SECURITY FOR NEW CONSTRUCTION (NOV 2005)	12
2. 0	AWARD FACTORS	13
2.1	ACCESSIBILITY AND SEISMIC SAFETY (SEP 2000)	
2.2	AWARD BASED ON PRICE (SEP 2000)	15
3. 0	MISCELLANEOUS	<i></i> .16
3.1	UNIT COSTS FOR ADJUSTMENTS	16
3.2	TENANT IMPROVEMENTS PRIOR TO THE GOVERNMENT'S INITIAL ACCEPTANCE OF SPACE (SEP 2000)	16
3.3	SUBSEQUENT TENANT IMPROVEMENTS \$100,000 OR LESS (SEP 2000)	17
3.4	ALTERNATE PROPOSALS	17
3.5	TAX ADJUSTMENT (SEP 2000)	17
3.6	PERCENTAGE OF OCCUPANCY	18
3.7	OPERATING COSTS (NCR variation (Nov 2001)	18
3.8	OPERATING COSTS BASE (SEP 2000)	19
3.9	RENTABLE SPACE (SEP 2000)	19
3.10	ANSI/BOMA OFFICE AREA SQUARE FEET (NCR VARIATION (aug 2002))	19
3.11	COMMON AREA FACTOR (SEP 2000)	19
3.12	APPURTENANT AREAS	19
3.13	LIQUIDATED DAMAGES, GSAR 552.270-15 (SEP 1999)	
3.14	VENDING FACILITIES (SEP 2000)	19
3.15	ADJUSTMENT FOR VACANT PREMISES, GSAR 552.270-16 (VARIATION) (SEP 1999)	20
3.16	RELOCATION ASSISTANCE ACT (Mar 2002)	
3.17	EVIDENCE OF CAPABILITY TO PERFORM (SEP 2000)	20
3.18	CONSTRUCTION SCHEDULE	20
3.19	CONSTRUCTION SCHEDULE OF TENANT IMPROVEMENTS (SEP 2000)	20
3.20		
3.21	PROGRESS REPORTS (SEP 2000)	
	CONSTRUCTION INSPECTIONS	22
3.21	REQUIRED PROOF OF AUTHORITY (ncr variation (aug 2002))	22
3.22	BUSINESS IMPROVEMENT DISTRICTS (B.I.D.) (ncr variation (aug 2002) )	
<b>4. 0</b> 4.1	GENERAL ARCHITECTUREQUALITY AND APPEARANCE OF BUILDING EXTERIOR (ncr vARIATION (AUG 2002))	23
4.1 4.2	CONSTRUCTION WASTE MANAGEMENT (SEP 2000)	
4.2 4.3		
4.3 4.4	EXISTING FIT-OUT, SALVAGED, OR RE-USED BUILDING MATERIAL (SEP 2000)	
4.4 4.5	INDOOR AIR QUALITY DURING CONSTRUCTION (SEP 2000)	
4.5 4.6	WORK PERFORMANCE (SEP 2000)	
4.0 4.7	BUILDING SYSTEMS (JAN 1997)	
4. <i>1</i> 4.8	SPACE EFFICIENCY (SEP 2000)	
4.0 4.9	CAD AS-BUILT FLOOR PLANS (NCR VARIATION (AUG 2002) )	20
	FLOORS AND FLOOR LOAD (SEP 2000)	
4.10 4.11	EXITS AND ACCESS (SEP 1991)	25
4.11	WINDOWS (NCR variation (AUG 2002))	
4.12	ACCESSIBILITY (SEP 2000)	25
4.13	LANDSCAPING (SEP 2000)	25
5. 0	ARCHITECTURAL FINISHES	26
5. 0 5.1	RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (SEP 2000)	26 26
5.1 5.2	ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS (SEP 2000)	26
V. <b>L</b>	ETT TO THE TIME LIMBLE DOLLING I NODOCTO AND WATERIALS (SEF 2000)	20

SFO NO.06-031 09/07/06

INITIALS: LESSOR & GOV'T

5.3	LAYOUT AND FINISHES	26
5.4	LAYOUT, FINISHES, AND COLORBOARDS (ncr variation (aug 2002) )	26
5.5	WOOD PRODUCTS (SEP 2000)	26
5.6	ADHESIVES AND SEALANTS (SEP 2000)	27
5.7	INSULATION: THERMAL, ACOUSTIC, AND HVAC (SEP 2000)	27
5.8	CEILINGS (SEP 2000)	27
5.9	WALL COVERINGS (SEP 2000)	27
5.10 5.11	PAINTING (SEP 2000)	28
5.12	DOORS: EXTERIOR (SEP 2000)	28
5.13	DOORS: SUITE ENTRY (SEP 2000)	28
5.14	DOORS: HARDWARE (NOV 2005)	20
5.15	DOORS: IDENTIFICATION (SEP 2000)	29
5.16	PARTITIONS: GENERAL (SEP 2000)	29
5.17	PARTITIONS: PERMANENT (SEP 2000)	29
5.18	PARTITIONS: SUBDIVIDING (SEP 2000)	29
5.19	FLOOR COVERING AND PERIMETERS (SEP 2000)	29
5.20	CARPET: BROADLOOM (SEP 2000)	30
5.21	CARPET TILE (SEP 2000)	30
5.22	ACOUSTICAL REQUIREMENTS (SEP 2000)	31
5.23	WINDOW COVERINGS (SEP 2000)	31
5.24	BUILDING DIRECTORY (SEP 2000)	32
5.25	FLAG POLE (SEP 2000)	32
6. 0	MECHANICAL, ELECTRICAL, PLUMBING	32
6.1	MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (SEP 2000)	32
6.2	ENERGY COST SAVINGS (SEP 2000)	32
6.3	DRINKING FOUNTAINS (SEP 2000)	32
6.4	TOILET ROOMS (SEP 2000)	32
6.5	TOILET ROOMS: FIXTURE SCHEDULE (SEP 2000)	33
6.6	JANITOR CLOSETS (SEP 2000)	
6.7 6.8	HEATING AND AIR CONDITIONING (SEP 2000)	34
6.9	VENTILATION (NCR VARIATION (AUG 2002)) VENTILATION: TOILET ROOMS (DEC 1993)	
6.10	ELECTRICAL: GENERAL (SEP 2000)	
6.11	ELECTRICAL: DISTRIBUTION (SEP 2000)	
6.12	ELECTRICAL: ADDITIONAL DISTRIBUTION SPECIFICATIONS	
6.13	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)	
6.14	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (SEP 2000)	36
6.15	DATA DISTRIBUTION (SEP 2000)	36
6.16	ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (SEP 2000)	36
6.17 6.18	ADDITIONAL ELECTRICAL CONTROLSELEVATORS (NCR VARiation (aug 2002))	37
6.19	LIGHTING: INTERIOR AND PARKING (NOV 2005)	31 37
6.20	LIGHTING: INTERIOR AND PARKING (NOV 2005)	38
7 0	SERVICES LITHER MANUFACTURE	
<b>7. 0</b> 7.1	SERVICES, UTILITIES, MAINTENANCE	
7.2	SERVICES, UTILITIES, MAINTENANCE: GENERAL (ncr variation (aug 2002) )	ەد دە
7.3	OVERTIME USAGE (SEP 2000)	30
7.4	UTILITIES	
7.5	BUILDING OPERATING PLAN	
7.6	JANITORIAL SERVICES (SEP 2000)	
7.7	SCHEDULE OF PERIODIC SERVICES (ncr variation (aug 2002) )	
7.8	LANDSCAPE MAINTENANCE	40
7.9	FLAG DISPLAY	
7.10	MAINTENANCE AND TESTING OF SYSTEMS (SEP 2000)	40
8. 0	SAFETY AND ENVIRONMENTAL MANAGEMENT	40
8.1	OCCUPANCY PERMIT (SEP 2000)	
8.2	FIRE AND LIFE SAFETY (SEP 2003)	
8.3	AUTOMATIC SPRINKLER SYSTEM ((NCR VARIATION) JUL 2004)	
8.4	FIRE ALARM SYSTEMS ((NCR VARIATION) JUL 2004)	
8.5	OSHA REQUIREMENTS (SEP 2000)	41
8.6	ASBESTOS (SEP 2000)	
8.7	INDOOR AIR QUALITY (SEP 2000)	
8.8	RADON IN AIR (SEP 2000)	42
	PADON IN WATER (SED 2000)	40
8.9 8.10	RADON IN WATER (SEP 2000)	42
8.10 8.11	RADON IN WATER (SEP 2000)	42

9. 0	LEASE SECURITY STANDARDS	42
9.1	GENERAL REQUIREMENTS (NOV 2005)	42
9.2	DETERRENCE TO UNAUTHORIZED ENTRY (NOV 2005)	43
9.3	ACCESS TO UTILITY AREAS (NOV 2005)	43
9.4	EMERGENCY POWER TO CRITICAL SYSTEMS (TENANT IMPROVEMENT) (NOV 2005)	43
9.5	MECHANICAL AREAS AND BUILDING ROOFS (NOV 2005)	43
9.6	ACCESS TO BUILDING INFORMATION (NOV 2005)	43
9.7	POSTING OF GOVERNMENT RULES AND REGULATIONS (TENANT IMPROVEMENT) (NOV 2005)	43
9.8	DEVELOPMENT, IMPLEMENTATION, AND PERIODIC REVIEW OF OCCUPANT EMERGENCY PLANS (NOV 2005)	43
9.9	EMERGENCY VOICE/ALARM COMMUNICATION SYSTEM (BUILDING SHELL) (NOV 2005)	43
9.10	BUILDING SECURITY PLAN (NOV 2005)	44
9.11	ADDITIONAL SECURITY MEASURES AS DETERMINED BY THE GOVERNMENT (NOV 2005)	44
9.12	BACKGROUND SECURITY CHECKS (NOV 2005)	44
9.13	ENTRY SECURITY: PUBLIC LOBBIES/ENTRANCES/EXITS (NOV 2005)	44
9.14	ENTRY SECURITY: SECURITY GUARDS (NOV 2005)	44
9.15	ENTRY SECURITY: X-RAY AND MAGNETOMETER AT PUBLIC ENTRANCES (NOV 2005)	45
9.16	ENTRY SECURITY: INTRUSION DETECTION SYSTEM WITH CENTRAL MONITORING CAPABILITY (NOV 2005)	45
9.17	ENTRY SECURITY: INTERCOM (NOV 2005)	45
9.18	ENTRY SECURITY: ENTRY CONTROL WITH CCTV AND DOOR STRIKES (TENANT IMPROVEMENT) (NOV 2005)	45
9.19	OCCUPANT/VISITOR SCREENING: PHOTO IDENTIFICATION (NOV 2005)	45
9.20	OCCUPANT/VISITOR SCREENING: VISITOR CONTROL/SCREENING SYSTEM (NOV 2005)	45
9.21	SECURE HVAC: OUTDOOR AIR INTAKES (BUILDING SHELL) (NOV 2005)	45
9.22	SECURE HVAC: AIRBORNE HAZARDS (NOV 2005)	46
9.23	SECURE HVAC: SECURE RETURN-AIR GRILLES (BUILDING SHELL) (NOV 2005)	46
9.24	PARKING SECURITY REQUIREMENTS (NOV 2005)	46
9.25	CCTV MONITORING: CCTV SURVEILLANCE CAMÉRAS WITH TIME LAPSE VIDEO RECORDING (NOV 2005)	46
9.26	CCTV MONITORING: POST SIGNS ADVISING OF 24-HOUR VIDEO SURVEILLANCE (TENANT IMPROVEMENT) (NOV 2005	)46
9.27	SHATTER-RESISTANT WINDOW PROTECTION REQUIREMENTS (NOV 2005) (BUILDING SHELL)	47
10.0	SPECIAL REQUIREMENTS	47
10.1	SPECIAL REQUIREMENTS:	47
SECUI	RITY: ADDITIONAL REQUIREMENTS	47

INITIALS: LESSOR & GOV'T

# 1.0 SUMMARY

# 1.1 AMOUNT AND TYPE OF SPACE (SEP 2000)

- A. The General Services Administration (GSÁ) is interested in leasing approximately 56,064 rentable square feet of space and 1,066 rentable square feet of of storage space. The rentable space shall yield 52,979 ANSI/BOMA Office Area (previously Usable) square feet, available for use by tenant for personnel, furnishings, and equipment and 1,066 ANSI/BOMA Office Area square feet of storage. Refer to the "ANSI/BOMA Office Area Square Feet" paragraph in the MISCELLANEOUS section of this Solicitation for Offers (SFO). In addition, the space shall include 13 on-site inside parking spaces which are designated and reserved, and 18 inside unreserved parking spaces.
- B. The Offer shall 1) be for space located in a quality building of sound and substantial construction as described in this SFO, 2) have a potential for efficient layout, 3) be within the square footage range to be considered, and 4) be in compliance with all of the Government's minimum requirements set forth herein. For purposes of this SFO, the definition of ANSI/BOMA Office Area square feet is in the "ANSI/BOMA Office Area Square Feet" paragraph in the MISCELLANEOUS section of this SFO.
- C. To demonstrate potential for efficient layout, the Offeror may be requested to provide a test fit layout at the Offeror's expense when the space offered contains certain features like:
  - 1. narrow column spacing;
  - 2. atriums, light wells, or other areas interrupting contiguous spaces;
  - 3. extremely long, narrow runs of space;
  - 4. irregular space configurations; or
  - 5. other unusual building features.
  - 6. The Government will advise the Offeror if the test fit layout demonstrates that the Government's requirement cannot be accommodated within the space offered. The Offeror will have the option of increasing the ANSI/BOMA Office Area square footage offered, provided that it does not exceed the maximum ANSI/BOMA Office Area square footage in this SFO. If the Offeror is already providing the maximum ANSI/BOMA Office Area square footage and cannot house the Government's space requirements, then the Government will advise the Offeror that the offer is unacceptable.
- D. Unless otherwise noted, all references in this SFO to square feet shall mean ANSI/BOMA Office Area square feet.

# 1.2 AREA OF CONSIDERATION (JUL 2005)

"White House Zone"

North: H Street, NW South: Constitution Avenue

East: 14th Street West: 18<sup>th</sup> Street

# 1.3 LOCATION: CITY CENTER (NCR VARIATION (JUNE 2006)

## A. NEIGHBORHOOD:

Space shall be located in a prime commercial office district with attractive, prestigious, professional surroundings with a
prevalence of modern design and/or tasteful rehabilitation in modern use. Streets and public sidewalks shall be
well-maintained.

# B. PARKING:

 The parking-to-square-foot ratio available on-site shall at least meet current local code requirements, or in the absence of a local code requirement, on-site parking shall be available at a ratio of 2.7 space for every 1000 rentable square feet of Government-demised area.

## C. LOCATION AMENITIES:

a. A variety of inexpensive fast food and moderately priced sit-down cafeteria or table service restaurants must be located within 2,500 walkable linear feet; and a variety of other employee services such as retail shops, cleaners, banks, etc., must be located within 2,500 walkable linear feet. To meet this requirement, amenities must be existing or the offeror must demonstrate to the reasonable satisfaction of the Government (i.e. through evidence of signed leases, construction contracts, etc.) that such amenities will exist by the Government's required occupancy date.

## 1.4 UNIQUE REQUIREMENTS


ONDCP has a preference for contiguous floors on a maximum of 5 separate floors.

SFO NO.06-031 09/07/06 INITIALS

I ESSOP

GOVIT

5



 One secured parking space is required. This parking space should be enclosed with CMU walls and have a dedicated garage door for security.

ONDCP will require the Lessor to accommodate surveillance system as described in the attachment. This will include exterior roof
cameras, cabling and public address speakers in the basement of the building.

The Lessor's building will accommodate a 24/7 ONDCP Security presence.

 Some program requirements require 24/7 HVAC. These include the Video-Teleconferencing areas, Communications Center, Telecommunications Control Room, Computer LAN room, Conference Rooms, Copy Room, Security Guard Stations, and Training Room.

See also Section 10 - "Special Requirements"

### 1.5 LEASE TERM (SEP 2000)

The lease term is for 5 years. All the terms and conditions contained herein shall prevail throughout the term of the lease.

### 1.6 OFFER DUE DATE

Offers are due by September 18, 2006 and shall remain open until award.

# 1.7 OCCUPANCY DATE (SEP 2000)

Occupancy is available for the SCIF facility by October 30, 2006. Occupancy is required for the remaining areas by March 30, 2007.

# 1.8 HOW TO OFFER (NCR VARIATION (JUL 2006))

A. Offers shall be submitted to the Contracting Officer at:

Tawanda Beverly Potomac Service Center General Services Administration 301 7th Street SW, Room 6646 Washington, DC 20407

And

Matt Witlin The Staubach Company, NE – Inc. 575 7<sup>th</sup> Street, NW Suite 400 Washington DC 20004

- B. The following documents, properly executed, shall be submitted no later than the close of business on the offer due date.
  - 1. SFO.
  - 2. SFO Attachments:
    - a. Attachment #1 -- Rate Structure
    - b. Attachment #2 Offeror's Pre-Lease Building Security Plan for an Office Building
    - c. Attachment #3 Small Business Subcontracting Plan
    - d. Attachment #4 Fire Protection and Life Safety Evaluation. In all cases, the offeror agrees to correct any deficiencies identified by the Government at the offeror's sole cost and expense prior to the Government's acceptance of the space and lease commencement.
  - 3. GSA Form 1364, Proposal to Lease Space.
  - 4. GSA Form 1217, Lessor's Annual Cost Statement.

Column A of the GSA Form 1217, Line 31(a) will be used to reflect any agreement between LESSOR AND the Lessor Representative agent(s), broker(s), property manager, developer, employee, or any other agent or representative (expressed in either % or \$) and Line 31(b) will reflect the agreement between LESSOR AND the GSA Tenant Representative broker (expressed in either % or \$).

INITIALS:


LESSOR

& GOV'T

- GSA Form 3517, General Clauses.
- 6. GSA Form 3518, Representatives and Certifications.
  - 7. First generation blue-line plans of the space offered, scaled at 1/8" = 1'-0" (preferred) or larger on CAD in accordance with SFO Paragraph entitled Plans with Offers.
- Photostatic copies are not acceptable. All architectural features of the space shall be accurately shown. If conversion or renovation of the building is planned, alterations to meet this SFO shall be indicated. If requested, more informative plans shall be provided within \_ 10 \_ days.
- Plans shall reflect corridors in place or the proposed corridor pattern for both a typical full (single-tenant) floor and/or partial (multi-tenant) floor. The corridors in place or proposed corridors shall meet local code requirements for issuance of occupancy permits.
- GSA will review the corridors in place and/or proposed corridor pattern to make sure that these achieve an acceptable level of safety as well as to ensure that these corridors provide public access to all essential building elements. The Offeror will be advised of any adjustments that are required to the corridors for the purpose of determining the ANSI/BOMA Office Area space. The required corridors may or may not be defined by ceiling-high partitions. Actual corridors in the approved layout for the successful Offeror's space may differ from the corridors used in determining the ANSI/BOMA Office Area square footage for the lease award.
- An hourly overtime rate for overtime use of heating and cooling. Refer to the "Overtime Usage" paragraph in the SERVICES, UTILITIES, MAINTENANCE section of this SFO. If proposed rate is different than recommended by an independent Government estimate, the Offeror may be required to submit worksheets justifying overtime energy usage and rates.
- Any other information (such as a fact sheet, 5" wide x 3" high or larger color photograph, site plan, location map, and tax parcel map) in case of multiple tax parcels for an offered building, etc., in order for the Government to perform a complete and adequate analysis of the offered property. Such information may also be requested by the Government, and in such circumstances, shall be submitted by the Offeror within 5 working days of the request.
- 10. Written acknowledgement and permission to represent other owners for the same SFO if a leasing agent or owner's representative is presenting buildings for multiple ownership groups.
- If applicable, the agents' disclosure and authorization from each ownership entity to offer in this SFO and/or represent multiple buildings with different ownerships, which may have conflicting interests. Owners and agents in conflicting interest situations are advised to exercise due diligence with regard to ethics, independent pricing, and Government procurement integrity requirements. In such cases, the Government reserves the right to negotiate with the owner directly.
- Documents supporting evidence of capability to perform. Refer to the "Evidence of Capability to Perform" paragraph in the MISCELLANEOUS section of this SFO.
- 13. Any Brokerage Commission Agreement between GSA's Tenant Representative and the Lessor for commissions identified in the GSA Form 1217 (July 94).
- 14. GSA will not conduct discussions nor will it consider an offer for award if the space offered is subject to a lease option held by other parties, including, but not limited to, a right of first offer or refusal. Offerors must certify, in writing, that no such option encumbers the space offered to GSA.
- C. Refer to GSA Form 3516, Solicitation Provisions, for additional instructions. If additional information is needed, the Contracting Officer (or the Contracting Officer's designated representative) should be contacted.
- D. There will be no public opening of offers, and all offers will be confidential until the lease has been awarded. However, the Government may release proposals outside the Government to a Government-support contractor to assist in the evaluation of offers. Such Government contractors shall be required to protect the data from unauthorized disclosure. The Offeror who desires to maximize protection of information in the offer may apply the restriction notice to the offer as described in GSA Form 3516, Solicitation Provision, 552.270-1 (d), Restriction on Disclosure and Use of Data.

# E. IMPORTANT CLARIFICATIONS TO OFFER REQUIREMENTS:

- Rate structure required from subparagraph B shall include the following:
  - A lease rate per square foot for the building shell rental, fully serviced. It is the intent of the Government to lease a building shell with a Tenant Improvement Allowance. All improvements in the base building, lobbies, common areas, and core areas shall be provided by the Lessor, at the Lessor's expense. This rate shall include, but not limited to, property financing (exclusive of Tenant Improvement), insurance, taxes, management, profit, etc., for the building. The building shell rental rate shall also include all basic building systems and common area buildout, including base building lobbies, common areas, and core areas, etc., exclusive of the ANSI/BOMA Office Area space offered as required in this SFO.
  - The annual cost (per usable and rentable square foot) for the cost of services and utilities. This equals line 27 of GSA Form 1217, Lessor's Annual Cost Statement, divided by the building size (shown on the top of both GSA Form 1364, Proposal to Lease Space, and Form 1217) for usable and rentable square feet respectively.



- The annual amortized cost of the Tenant Improvement Allowance. Such amortization shall be expressed as a cost per usable and rentable square foot per year. Tenant Improvements shall be all alterations for the Government-demised area above the building shell buildout. The Tenant Alteration Allowance shall be \$5.00 per ANSI/BOMA Office Area square foot, with an option to add more. The Landlord is required to submit various submit various tenant improvement packages and schedules. Such alterations shall be described and identified in the drawings used to construct the Government-demised area. The Tenant Alteration Allowance, which is to be provided by the Lessor to the Government for Tenant Improvements, shall be made available at lease execution.
- A fully-serviced lease rate per usable and rentable square foot as a summation of the amounts broken out in the subparagraphs a, b, and d for the lease.
- A fully-serviced lease rate per usable and rentable square foot for that portion of the lease term extending beyond the firm term. The rate proposed for this portion of the term shall not reflect any Tenant Improvements as they will have been fully amortized over the firm term


#### 1.9 BUILDING SHELL REQUIREMENTS (NCR VARIATION (AUG 2002))

A. The Government currently leases the Premises under Lease No. GS-11B-01533. The Building will be delivered to Tenant "as-is" unless specifically noted otherwise. The Government shall have the right to make non-structural improvements, at Government expense and in accordance with Government security standards, to the interior of the premises, in a good and workmanlike manner, in comformity with all laws, ordinances and regulations of public authorities having jurisdiction. Tenant shall not make any alterations to the foundation, roof, or structural portions of the premises without first obtaining the approval of the landlord. Such approval shall may not be unreasonably withheld and shall be deemed granted if the Government is not notified in writing of reasonalble basis for withholding such approval within ten (10) days of notifying the Landlord thereof. It is further agreed that upon termination of this lease, the Government may remove its furniture, fixtures and equipment and Landlord will accept the premises as altered without any obligation upon the Government to restore the premises to its former conditions.

The Lessor's buildout obligations in providing a building shell (at the Lessor's expense) shall be furnished, installed and coordinated with Tenant Improvements and shall include the following:

- Base structure and building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stairwells, elevators, garages, and services areas, shall be complete. Restrooms shall be complete and operational. All newly installed building shell components, including but not limited to, heating, ventilation, and air conditioning (HVAC), electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with Tenant Improvements. Circulation corridors are provided as part of the base building only on multi-tenanted floors where the corridor is common to more than one tenant. On single tenant floors, only the fire egress corridor necessary to meet code is provided as part of the shell.
- 2. Accessibility Requirements. Accessibility to persons with disabilities shall be required throughout the common areas accessible to Government tenants in accordance with both the ADAAG and the UFAS and shall be installed and coordinated with Tenant Improvements. Refer to the "Accessibility" paragraph and the "Accessibility and Seismic Safety" paragraph in the AWARD FACTORS section of this SFO.
- 3. Ceilings. A complete acoustical ceiling system (which includes grid and lay-in tiles) throughout the Government-demised area and all common areas accessible to Government tenants shall be required in accordance with the "Ceilings" paragraph in the ARCHITECTURAL FINISHES section of this SFO. The acoustical ceiling system shall be furnished, installed, and coordinated with Tenant Improvements.
- 4. Doors. Exterior building doors and doors necessary to the lobbies, common areas, and core areas shall be required. This does not include suite entry or interior doors specific to Tenant Improvements. Related hardware shall be installed in accordance with the "Doors: Hardware" paragraph and the "Doors: Exterior" paragraph in the ARCHITECTURAL FINISHES section of this SFO.
- 5. Partitions. Permanent, perimeter, and demising slab-to-slab partitions (including all columns) finished with paint and base shall be required in accordance with the "Partitions: General" paragraph and the "Partitions: Permanent" paragraph in the ARCHITECTURAL FINISHES section of this SFO.
- 6. Flooring. All building common areas shall have finished floors in accordance with the "Floor Covering and Perimeters" paragraph in the ARCHITECTURAL FINISHES section of this SFO. The offeror shall provide a broom clean concrete floor slab, with level floor not varying more than 1/4" over ten (10) foot horizontal run in accordance with American Concrete Institute (ACI) Standards.
- 7. Plumbing. The Offeror shall include cost of plumbing in common areas, such as for toilet rooms and janitor closets as part of the building shell cost. Hot and cold water risers and domestic waste and vent risers, installed and ready for connections that are required for Tenant Improvements, shall be included in the shell rent.
- 8. HVAC. Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all building common areas. Conditioned air

INITIALS: & & &



- 9. Electrical. Electrical power distribution panels and circuit breakers shall be available in an electrical closet, with capacity at 277/480 volt (V) and 120/208 V, 3-phase, 4-wire system providing 7 watts (W) per ANSI/BOMA Office Area square foot.
- 10. Lighting. Parabolic type 2'-0" wide x 2'-0" high fluorescent lighting fixtures (or other building standard fixtures) shall be installed in the ceiling grid for an open office plan at the rate of 1 fixture per 80 ANSI/BOMA Office Area square feet. Lighting as necessary shall be provided in all building common areas in accordance with the "Lighting: Interior and Parking" paragraph in the MECHANICAL, ELECTRICAL, PLUMBING section of this SFO.
- 11. Safety and Environmental Management. Complete safety and environmental management shall be provided throughout the building in accordance with federal, state, and local codes and laws including, but not limited to, such items as fire detection and alarms, emergency building power for life safety systems, etc., and shall be in accordance with both the ADAAG and the UFAS. Where sprinklers are required in the Government-demised area, sprinkler mains and distribution piping in a "protection" layout (open plan) with heads turned down with an escutcheon or trim plate shall be provided.
- 12. Telephone Rooms. Building telecommunication rooms on each floor shall be completed, operational, and ready for Tenant Improvements. The telephone closets shall include a telephone backboard. Vertical conduit (empty sleeve) through building core, available for tenant wiring/cabling.
- 13. Architectural/Engineering Design. All architectural and engineering costs associated with the building shell requirements shall be included in the building shell rate.
- 14. Demolition. Any demolition of existing improvements which is necessary to satisfy the Government's layout shall be done at the Lessor's expense.
- 15. Any alterations necessary for the building shell to meet the SFO requirements shall be included in the building shell rate.
- 16. All of the above improvements are described in more detail hereinafter in this SFO.

### 1.10 TENANT IMPROVEMENTS (SEP 2000)

- A. The Tenant Improvement Allowance shall be used for building out the Government-demised area in accordance with the Government-approved design intent drawings. All Tenant Improvements required by the Government for occupancy shall be performed by the successful Offeror as part of the rental consideration, and all improvements shall meet the quality standards and requirements of this SFO and GSA Form 3517. General Clauses.
- B. The Tenant Improvement Allowance shall include all the Offeror's administrative costs, general contractor fees, subcontractor's profit and overhead costs, Offeror's profit and overhead, design costs, and other associated project fees necessary to prepare construction documents to complete the Tenant Improvements. It is the successful Offeror's responsibility to prepare all documentation (working drawings, etc.) required to receive construction permits. NO COSTS ASSOCIATED WITH THE BUILDING SHELL SHALL BE INCLUDED IN THE TENANT IMPROVEMENT PRICING.

# 1.11 TENANT IMPROVEMENT RENTAL ADJUSTMENT (SEP 2000)

- A. All Tenant Improvements shall be identified after award of the contract in accordance with the provisions established in the "Design Intent Drawings" subparagraph in the "Construction Schedule of Tenant Improvements" paragraph in the MISCELLANEOUS section of this SFO.
  - The Government, at its sole discretion, shall make all decisions as to the usage of the Tenant Improvement Allowance. The Government may use all or part of the Tenant Improvement Allowance. The Government may return to the Lessor any unused portion of the Tenant Improvement Allowance in exchange for a decrease in rent according to the amortization rate over the firm term.
  - 2. The Government reserves the right to make cash payments for any or all work performed by the Lessor. Prior to occupancy, the Government, at its sole discretion, may choose to pay lump sum for any or all of the Tenant Improvement Allowance. If, prior to occupancy, the Government elects to make a lump sum payment for any portion of the Tenant Improvement Allowance by the Government will result in a decrease in the rent. At any time after occupancy, the Government, at its sole discretion, may choose to pay lump sum for any part or all of the remaining unpaid amortized balance of the Tenant Improvement Allowance. If the Government elects to make a lump sum payment for the Tenant Improvement Allowance after occupancy, the payment of the Tenant Improvement Allowance by the Government will result in a decrease in the rent according to the amortization rate over the firm term of the lease
  - 3. If it is anticipated that the Government will spend more than the allowance identified above, the Government reserves the right to 1) reduce the Tenant Improvement requirements, 2) pay lump sum for the overage upon completion and acceptance of the improvements, or 3) increase the rent according to the negotiated amortization rate over the firm term of the lease.
  - 4. Payment will not be made by the Government in instances where the Government accepts fixtures and/or other Tenant Improvements already in place. However, the Lessor will be reimbursed for costs to repair or improve the fixture(s) and/or any other improvements already in place.

INITIALS: LESSOR & COVT

SFO NO.06-031 09/07/06

#### 1.12 **PLANS WITH OFFER (SEP 2000)**

All plans submitted for consideration shall have been generated by a Computer Aided Design (CAD) program which is compatible with the latest release of AutoCAD. The required file extension is DWG. Clean and purged files shall be submitted on 3-1/2-inch double-sided, high density diskettes, or, if approved by the Contracting Officer, on CD-ROM. All submissions shall be accompanied with a written matrix indicating the layering standard to ensure that all information is recoverable. Plans shall include a proposed corridor pattern for typical floors and/or partial floors. All architectural features of the space shall be accurately shown. By the offer due date, existing floor plans shall be submitted.

### 1.13 **BROKER COMMISSION AND COMMISSION CREDIT (JUL 2006)**

A. For the purposes of this SFO, The Staubach Company (the Broker) is the authorized real estate broker representing GSA. A GSA Contracting Officer must review, approve, and execute the Lease. The government expects the Lessor to pay a commission to the Broker. By submitting an offer, the Lessor agrees that if the Lessor is paying a commission or fee in connection with this lease transaction to a listing agent, an offering agent, or broker, property manager, developer, or any other agent or representative, then the Lessor will pay a commission to the Broker that it normally would be entitled to pursuant to local business practices, as evidenced through a brokerage agreement between the Lessor and the Broker. The commission will be based on a lease term not to exceed the firm term of the lease contract. Commissions will not be negotiated or collected on option periods or for lease terms beyond the firm term of the lease. The Lessor agrees that the commission to be paid to the Broker shall be paid not later than the Lease Commencement date as defined in the "Construction Schedule of Tenant Improvements" paragraph in the MISCELLANEOUS section of this SFO. As part of the offer, the offeror shall disclose any and all commissions and/or fees to be paid by the Lessor including both the Lessor's agent(s), broker(s), property manager, developer or any other agent or representative and the Broker.

Paragraphs B & C are not applicable to expedited lease transactions as defined by the National Broker Contract.

- B. For the benefit of the Government, the Broker has agreed to forego 31 percent of the commission that it is entitled to receive in connection with this lease transaction. The resulting total dollar value of the foregone commission (the Commission Credit) shall be applied in equal monthly amounts against shell rental payments due and owing under the Lease. The rental amount payable shall be reduced by the Commission Credit at the commencement of the Lease, over the minimum number of months that will not exceed the monthly shell rental, until the Commission Credit has been fully recaptured. The parties agree to execute a Supplemental Lease Agreement setting forth the full nature, extent, terms, and conditions of commissions paid to the Broker and the Commission Credit to be applied against the Government's rental payment obligations under the Lease.
- C. For purposes of price evaluation, the Commission Credit shall be treated as a deduction from the rent in accordance with the "Price Evaluation" paragraph in the SUMMARY section of this SFO. The amount of the commission paid to GSA's Broker shall not be considered separately as part of this price evaluation since the value of the commission is subsumed in the gross rent rate.

### **NEGOTIATIONS (MAY 2005)** 1.14

- Negotiations will be conducted on behalf of the Government by the Contracting Officer (or the Contracting Officer's designated representative). The Contracting Officer is named on the cover of this SFO. GSA will negotiate rental price for the initial term, any renewal periods, and any other aspect of the offer as deemed necessary.
- B. The Offeror shall not enter into negotiations concerning the space leased or to be leased with representatives of federal agencies other than the Contracting Officer or designee.
- C. The Contracting Officer or their designated representative will conduct oral or written negotiations with all Offerors that are within the competitive range. The competitive range will be established by the Contracting Officer on the basis of cost or price and other factors (if any) that are stated in this SFO and will include all of the most highly rated proposals, unless the range is further reduced for purposes of efficiency. Offerors who are not included in the competitive range will be notified in writing.
- D. All Offerors will be provided a reasonable opportunity to submit any cost or price, technical, or other revisions to their offer that may result from the negotiations. Negotiations will be closed with submission of final proposal revisions ("Best and Final" offers).

### 1.15 PRICE EVALUATION (PRESENT VALUE) (NCR VARIATION (MAY 2005))

A. If annual CPI adjustments in operating expenses are included, the Offeror shall be required to submit the offer with the total "gross" annual price per rentable square foot and a breakout of the "base" price per rentable square foot for services and utilities (operating expenses) to be provided by the Lessor. The "gross" price shall include the "base" price.

- В. The Offeror shall be required to submit plans and any other information to demonstrate that the rentable space yields ANSI/BOMA Office Area space within the required ANSI/BOMA Office Area range. The Government will verify the amount of ANSI/BOMA Office Area square footage and will convert the rentable prices offered to ANSI/BOMA Office Area prices, which will subsequently be used in the price evaluation.
- If the offer includes annual adjustments in operating expenses, the base price per ANSI/BOMA Office Area square foot from which C. adjustments are made will be the base price for the term of the lease, including any option periods.

INITIALS: LESSOR & DA

- D. Evaluation of offered prices will be on the basis of the annual price per ANSI/BOMA Office Area square foot, including any option periods. The Government will perform present value price evaluation by reducing the prices per ANSI/BOMA Office Area square foot to a composite annual ANSI/BOMA Office Area square foot price, as follows:
  - 1. Parking and wareyard areas will be excluded from the total square footage but not from the price. For different types of space, the gross annual per square foot price will be determined by dividing the total annual rental by the total square footage minus these areas.
  - 2. Free rent will be evaluated in the year in which it is offered. The gross annual per square foot price is adjusted to reflect free rent
  - 3. Prior to the discounting procedure below, the total dollar amount of the Commission Credit (if applicable) will be subtracted from the first year's gross annual rent (unless the provision of free rent causes the credit to apply against rent beyond the first year's term, in which case the Commission Credit will be allocated proportionately against the appropriate year's gross rent.
  - 4. Also as stated in the "Broker Commission and Commission Credit" paragraph, the amount of any commission paid to GSA's Broker will not be considered separately as part of this price evaluation since the value of the commission is subsumed in the gross rent rate.
  - 5. If annual adjustments in operating expenses will not be made, the gross annual per square foot price, minus the Commission Credit (if applicable), will be discounted annually at 5 percent to yield a gross present value cost (PVC) per square foot.
  - 6. If annual adjustments in operating expenses will be made, the annual per square foot price, minus the Commission Credit (if applicable) and the base cost of operating expenses, will be discounted annually at 5 percent to yield a net PVC per square foot. The operating expenses will be both escalated at 2.5 percent compounded annually and discounted annually at 5 percent, then added to the net PVC to yield the gross PVC.
  - 7. To the gross PVC will be added:
    - The cost of Government-provided services not included in the rental escalated at 2.5 percent compounded annually and discounted annually at 5 percent.
    - b. The annualized (over the full term) per ANSI/BOMA Office Area square foot cost of any items, which are to be reimbursed in a lump sum payment. (The cost of these items is present value; therefore, it will not be discounted.)
    - The cost of relocation of furniture, telecommunications, replications costs, and other move-related costs, if applicable.
    - d. The annual cost of overtime heating and cooling, per ANSI/BOMA Office Area square foot, discounted annually at 5 percent. The cost of overtime heating and cooling will be determined by multiplying the rate submitted by the Offeror by the Government's projected use of \_\_100\_ overtime hours per year with the result converted to a price per ANSI/BOMA Office Area square foot. The actual amount of overtime hours used during the year may differ from the projected use. The Government will make a lump sum payment for only the actual number of overtime hours used during the year.
    - The sum of either subparagraphs 5 and 7 or subparagraphs 6 and 7 will be the ANSI/BOMA Office Area per square foot present value of the offer for price evaluation purposes.

### 1.16 **AWARD (JAN 1997)**

- A. After conclusion of negotiations, the Contracting Officer will require the Offeror selected for award to execute the proposed lease prepared by GSA which reflects the proposed agreement of the parties.
- B. The proposed lease shall consist of:
  - 1. Standard Form 2 (or GSA Form 3626) U.S. Government Lease for Real Property,
  - 2. required clauses.
  - 3. required certifications and representations,
  - 4. the pertinent provisions of the offer, and
  - 5. the pertinent provisions of the SFO.
- C. The acceptance of the offer and award of the lease by the Government occurs upon notification of unconditional acceptance of the offer or execution of the lease by the Contracting Officer and mailing or otherwise furnishing written notification or the executed lease to the successful Offeror.

INITIALS: & SOUT

#### 1.17 **LABOR STANDARDS (AUG 2003)**

A. If an Offeror proposes to satisfy the requirements of this SFO through the construction of a new building or the complete rehabilitation or reconstruction of an existing building, and the Government will be the sole or predominant tenant such that any other use of the building will be functionally or quantitatively incidental to the Government's use and occupancy, the following Federal Acquisition Regulation (FAR) clauses shall apply to all work (including base building and tenant buildout) performed prior to the Government's acceptance of space as substantially complete. Full text versions of these clauses are available upon request from the Contracting Officer. Full text versions are also available at the following web site: http://www.arnet.gov/far/

52.222-4	Contract Work Hours and Safety Standards Act - Overtime Compensation
52.222-6	Davis-Bacon Act
52.222-7	Withholding of Funds
52.222-8	Payrolls and Basic Records
52.222-9	Apprentices and Trainees
52.222-10	Compliance with Copeland Act Requirements
52.222-11	Subcontracts (Labor Standards)
52.222-12	Contract Termination-Debarment
52.222-13	Compliance with Davis-Bacon and Related Act Regulations
52.222-14	Disputes Concerning Labor Standards
52.222-15	Certification of Eligibility

#### 1.18 **SECURITY FOR NEW CONSTRUCTION (NOV 2005)**

- A. The requirements of this SFO can only be satisfied through the construction of a new building that fully complies with the lease security standards as described in this SFO and its attachments.
- B. For those buildings described in subparagraph A, the Offeror shall provide a written certification from a licensed professional engineer that the building(s) conforms with a minimum of:
  - Window glazing, with a performance condition as specified in this SFO, as prescribed by WINGARD 4.1 or later or WINLAC 4.3 software.
  - Facade protection level, with a performance condition as specified in this SFO, as prescribed by WINGARD 4.1 or later or WINLAC 4.3 software.
  - 3. Setback distance, as specified in this SFO, from the face of the building's exterior to the protected/defended perimeter (i.e., any potential point of explosion). This means the distance from the building to the curb or other boundary protected by bollards, planters or other street furniture. Such potential points of explosion may be, but are not limited to, such areas that could be accessible by any motorized vehicle (i.e., street, alley, sidewalk, driveway, parking lot).
  - Lobbies, mailrooms, and loading docks shall not share a return-air system with the remaining areas of the building. The Lessor shall provide lobby, mailroom, and loading dock ventilation systems' outside air intakes and exhausts with low leakage, fast acting, isolation dampers that can be closed to isolate their systems. Dedicated HVAC shall be required for mailrooms only when the Government specifically requires a centrally operated mailroom. On buildings of more than four stories, air intakes shall be located on the fourth floor or higher. On buildings of three stories or less, air intakes shall be located on the roof or as high as practical. Locating intakes high on a wall is preferred over a roof location.
- C. The Offeror shall provide a Pre-Lease Building Security Plan (BSP) with its offer that addresses its compliance with the lease security standards, as described in this SFO and its attachments.
- D. The Offeror shall provide the Government with all design and engineering documents, including structural engineering calculations.
- E. Offers must include an itemized estimate for the costs of each security item identified as "shell" in Section 9, "Lease Security Standards," and for any security item in Section 10, "Special Requirements," below.

INITIALS: LESSOR & GOVT

# 2.0 AWARD FACTORS

# 2.1 ACCESSIBILITY AND SEISMIC SAFETY (SEP 2000)

- A. All offers received in response to this SFO will be evaluated to determine whether the offers fully meet National Institute of Standards and Technology (NIST) NISTIR 5382, Interagency Committee on Seismic Safety in Construction (ICSSC) RP 4, Standards of Seismic Safety for Existing Federally Owned or Leased Buildings, as modified below, and the accessibility requirements for new construction of the Americans With Disabilities Act Accessibility Guidelines (ADAAG) (Code of Federal Regulations 36 CFR Part 1191, App. A) and the Uniform Federal Accessibility Standards (UFAS) (Federal Register vol. 49, No. 153, August 7, 1984, reissued as FED. STD. 795, dated April 1, 1988, and amended by Federal Property Management Regulations CFR 41, Subpart 101-19.6, Appendix A, 54 FR 12628, March 28, 1989). Where standards conflict, the more stringent shall apply. If any offers are received which fully meet accessibility and seismic safety requirements, then other offers, which do not fully meet these requirements, will not be considered.
- B. The following UFAS provisions are clearly more stringent than the ADAAG:
  - Work Areas. The UFAS requires that all areas be accessible where there may be employment of persons with disabilities.
    The ADAAG requires only that people with disabilities be able to approach, enter, and exit a work area. [UFAS 4.1.4;
    ADAAG 4.1.1(3)]
  - Work Surface Scoping. The UFAS requires that 5 percent of all fixed or built-in employee work surfaces be accessible. The ADAAG does not require work surfaces in work areas to be accessible. Both the UFAS and the ADAAG require that 5 percent of fixed tables in public or common use areas be accessible. [UFAS 4.1.2(17) and 4.32; ADAAG 4.1.1(3) and 4.1.3(18)]
  - No Elevator Exception. The UFAS has no exception to the elevator requirement in all multi-story buildings and facilities.
    The ADAAG provides an exception to the elevator requirement in certain buildings that are under three stories or have less than 3,000 square feet per story. [UFAS 4.1.2(5); ADAAG 4.1.3(5) Exception 1]
  - 4. Entrances in Multi-Grade Buildings. The UFAS requires at least one principle entrance at each grade floor to a building to be accessible. The ADAAG requires that 1) at least 50 percent of all public entrances be accessible and 2) the number of exits required by the applicable building/fire code be used in determining the total number of accessible entrances required in a building or facility. The UFAS requires more accessible entrances in certain multi-grade buildings. [UFAS 4.1.2.(8); ADAAG 4.1.3(8)]
  - Elevator Controls. The UFAS requires elevator controls to be mounted no higher than 48 inches "unless there is a substantial increase in cost," in which case 54 inches is allowed. The ADAAG allows 54 inches whenever a parallel approach is provided. [UFAS 4.10.12(3); ADAAG 4.10.12(3)]

# C. FULL COMPLIANCE:

- 1. "Fully meets" as used herein with regard to the accessibility requirements means the offer fully complies with both the ADAAG and the UFAS requirements for new construction, including but not limited to: Parking and Passenger Loading Zones, Accessible Route, Entrance and Egress, Ramps, Stairs, Handrails, Doors, Elevators, Telephones, Controls, Signage, Alarms, Drinking Fountains, Storage Facilities, Seating and Workstations, Assembly Areas, and Toilet Rooms. Where standards conflict, the more stringent shall apply.
- 2. "Fully meets" as used herein with regard to the seismic safety requirements means that the Offeror has provided a written certification (example available for the Contracting Officer) from a licensed structural engineer certifying that both the building design and construction are in full compliance with the life-safety performance level of NISTIR 5382, ICSSC RP 4, Standards of Seismic Safety for Existing Federally Owned or Leased Buildings, AS MODIFIED HEREIN:
  - FEMA-178, NEHRP Handbook for the Seismic Evaluation of Existing Buildings, shall be replaced with FEMA-310, Handbook for the Seismic Evaluation of Buildings: A Prestandard.

INITIALS: \_\_\_\_\_\_ & B

LESSOR

GOVT

b. Section 1.3.1, Post-Benchmark Buildings (Table 1: Advisory Benchmark Years) shall be replaced with the below

	Model Building Seismic Design Provisions			
BUILDING TYPE <sup>1</sup>	BOCA <sup>IS</sup>	SBCCI	UBC	
Wood Frame, Wood Shear Panels (Type W1 and W2) <sup>2</sup>	1992	1993	1976	
Wood Frame, Wood Shear Panels (Type W1A)	1992	1993	1976	
Steel Moment Resisting Frame (Type S1 and S1A)	**	**	1994⁴	
Steel Braced Frame (Type S2 and S2A)	1992	1993	1988	
Light Metal Frame (Type S3)	*	*	*	
Steel Frame w/Concrete Shear Walls (Type S4)	1992	1993	1976	
Reinforced Concrete Moment Resisting Frame (Type C1) <sup>3</sup>	1992	1993	1976	
Reinforced Concrete Shear Walls (Type C2 and C2A)	1992	1993	1976	
Steel Frame with URM Infill (Type S5 and S5A)	*	*	*	
Concrete Frame with URM Infill (Type C3 and C3A)	*	*	*	
Tilt-up Concrete (Type PC1 and PC1A)	*	*	1997	
Precast Concrete (Type PC2 and PC2A)	*	*	*	
Reinforced Masonry (Type RM1)	*	*	1997	
Reinforced Masonry (Type RM2)	1992	1993	1976	
Unreinforced Masonry (Type URM) <sup>5</sup>	*	*	1991⁵	
Unreinforced Masonry (Type URMA)	*	*	*	

- Building Type refers to one of the Common Building Types defined in Table 2-2 of FEMA-310.
- Buildings on hillside sites shall not be considered Benchmark Buildings.
- Flat Slab Buildings shall not be considered Benchmark Buildings.
- Steel Moment-Resisting Frames shall comply with Section 2213.7.1.2 of the Uniform Building Code.
- URM buildings evaluated using the ABK Methodology (ABK, 1984) may be considered Benchmark Buildings.
- Refers to the UBCB Section of the UBC.
- Only buildings designed and constructed or evaluated in accordance with FEMA-310 and being evaluated to the Life-Safety Performance level may be considered Benchmark Buildings.
- No Benchmark year; building shall be evaluated using FEMA-310.
- Local provisions shall be compared with the UBC.

BOCA Building Officials and Code Administrators, *National Building Code*.

SBCCI Southern Building Code Congress International, *Standard Building Code*.

UBC International Conference of Building Officials, *Uniform Building Code*.

- c. Section 1.3.2, Leased Buildings, shall be revised as follows:
  - i. Buildings leased by the federal Government are exempt from these standards if both of the following apply:
    - (a) The leased space is less than 10,000 square feet AND
    - (b) The building is located in Regions of Low Seismicity in accordance with FEMA-310. According to FEMA-310, buildings located on sites for which the design short-period response acceleration, S<sub>s</sub>, is less than 0.167 gravity (g), or for which the design one-second period response acceleration, S<sub>1</sub>, is less than 0.067 g, shall be considered to be located within Regions of Low Seismicity.
- d. FEMA-310, Handbook for the Seismic Evaluation of Buildings: A Prestandard, can be obtained by calling the Federal Emergency Management Agency (FEMA) Distribution Center at (800) 480-2520.
- e. NISTIR 5382, ICSSC RP 4, Standards of Seismic Safety for Existing Federally Owned or Leased Buildings, can be obtained from the Building and Fire Research Laboratory, National Institute of Standards and Technology, Gaithersburg, MD 20899.

# D. SUBSTANTIAL COMPLIANCE:

- 1. In accordance with both the ADAAG and the UFAS, if no offer is received which fully meets accessibility requirements for new construction, but an offer(s) is received which substantially meets these requirements, then other offers which do not substantially meet these requirements will not be considered. "Substantially meets" as used herein with regard to the accessibility requirements means the offer fully complies with both the ADAAG and the UFAS requirements for Parking and Passenger Loading Zones, Accessible Route, Entrance and Egress, Doors, Drinking Fountains, Toilet Rooms.
- 2. "Substantially meets" as used herein with regard to the seismic safety requirements will be determined by the Government based upon the Offeror's evaluation by a licensed structural engineer that specifically describes all exceptions to full compliance with the Model Building Seismic Design Provisions as shown in the Benchmark Buildings table above. The Offeror shall evaluate the building by using FEMA-310 and shall identify all deficiencies. Based upon the evaluation, the Contracting Officer will make an award to the Offeror which best meets both the seismic safety requirements and the other requirements of this SFO. Documentation of this evaluation shall be made available to the Government.

INITIALS: LESSOR & COUT

SFO NO.06-031 09/07/06

14

# E. LESS THAN SUBSTANTIAL COMPLIANCE:

In accordance with both the ADAAG and the UFAS, if no offer is received which either fully or substantially meets the accessibility requirements of new construction, consideration will be given only to offers which meet the following minimum requirements:

- At least one accessible route shall be provided from an accessible entrance to the leased space and all required accessible areas. At least one interior means of vertical access shall be provided. Elevators shall have complying Controls and Signage.
- 2. If parking is provided, then accessible spaces shall be included.
- 3. Accessible toilet rooms shall be provided as follows:
  - Where more than one toilet room for each sex is provided on a floor on which the Government leases space, at least one toilet room for each sex on that floor shall be accessible.
  - Where only one toilet room for each sex is provided on a floor on which the Government leases space, either one b. unisex toilet room or one toilet room for each sex on that floor shall be accessible.
  - Where only one toilet room is provided in a building where the Government leases space, one unisex toilet room shall C.
  - In a qualified historic building where the Advisory Council on Historic Preservation determines that providing the above minimum accessible toilet facilities would threaten or destroy the historic integrity of the space, accessible unisex toilet room(s) shall be provided in the building.
- F. If no offer is received which meets the minimum accessibility requirements described above, offers will not be considered unless a waiver of accessibility requirements is requested by the Contracting Officer and granted by the GSA Public Buildings Service Commissioner.

### 2.2 **AWARD BASED ON PRICE (SEP 2000)**

The lease will be awarded to the responsible Offeror whose offer conforms to the requirements of this SFO and is the lowest priced offer submitted. Refer to the "Price Evaluation" paragraph in the SUMMARY section of this SFO.

INITIALS: LESSOR & COURT

# **MISCELLANEOUS**

#### 3.1 **UNIT COSTS FOR ADJUSTMENTS**

- A. The Offeror is required to state in the offer or in an attachment units prices for the items listed below. Prices shall be quoted as fully installed and finished. The unit prices may be used, upon acceptance by GSA, during the first year of the lease to price alterations costing \$100,000 or less. These prices may be indexed or renegotiated to apply to subsequent years of the lease upon mutual agreement of the Lessor and the Government.
  - The cost per linear foot of office subdividing ceiling-high partitioning.
  - 2. The cost per floor-mounted duplex electrical outlet.
  - 3. The cost per wall-mounted duplex electrical outlet.
  - 4. The cost per floor-mounted fourplex (double duplex) electrical outlet.
  - 5. The cost per wall-mounted fourplex (double duplex) electrical outlet.
  - The cost per dedicated clean electrical computer receptacle.
  - 7. The cost per floor-mounted telephone outlet.
  - 8. The cost per wall-mounted telephone outlet.
  - 9. The cost per interior door.

### 3.2 TENANT IMPROVEMENTS PRIOR TO THE GOVERNMENT'S INITIAL ACCEPTANCE OF SPACE (SEP 2000)

- The Lessor is required to provide cost or pricing data in conjunction with the Tenant Improvements as specified by the Government in GSA Form 3517, General Clauses.
- B. In lieu of submitting detailed cost or pricing data and entering into negotiations to determine a final cost for the subject work, the Government (in accordance with FAR 15.403) is willing to accept a price based upon the results of a competitive proposal process if the following conditions are met:
  - 1. The Lessor shall submit to the Government a proposal for overhead, profit, and architectural-engineering fees, permits, and regulatory fees for all Tenant Improvements.
    - This will be negotiated and agreed upon prior to the award for the subject improvements (separate from lease award).
  - 2. The scope of work includes the lease, the SFO, all SFO attachments, the construction drawings/documents, and written specifications. In cases of discrepancies, the Lessor shall immediately notify the Contracting Officer for resolution. All differences will be resolved by the Contracting Officer in accordance with the terms and conditions of the lease.
  - 3. No building shell items shall be included in the competitive proposal.
  - 4. A minimum of three qualified contractors shall be invited to participate in the competitive proposal process. Each participant shall compete independently in the process.
  - 5. Each proposal shall be 1) submitted in Construction Specifications Institute (CSI) format by the proposed contractors and 2) reviewed by the Government. The Government reserves the right to determine if bids meet with the scope of work, that the price is reasonable, and that the Offeror is qualified to perform the work. The Government reserves the right to reject all bids, at its sole discretion.
  - 6. The Government shall be represented at all negotiation sessions between the Lessor and potential contractors.
  - 7. The Lessor shall demonstrate to the Government that best efforts have been made to obtain the most competitive prices possible, and the Lessor shall accept responsibility for all prices through direct contracts with all contractors.
  - 8. The Lessor shall complete the competition and the cost proposal process in 21 working days or less from the date of issuance of completed construction documents. This will be considered the first 21 working days of the days allotted to "Review of Working/construction Drawings." Refer to the "Construction Schedule of Tenant Improvements" paragraph in the MISCELLANEOUS section of this SFO.
  - 9. Once the Government determines that there is adequate competition, and upon the Government's acceptance of the Lessor's cost proposal based upon that competition (provided the Lessor selects the competition's lowest priced bid of a contractor qualified to perform the subject work), the Contracting Officer shall issue to the Lessor a notice to proceed for the subject work.
  - 10. The Lessor shall complete the work within the time frame requirements illustrated in the "Construction Schedule of Tenant Improvements" paragraph in the MISCELLANEOUS section of this SFO.

INITIALS: LESSOR & COVIT

### 3.3 SUBSEQUENT TENANT IMPROVEMENTS \$100,000 OR LESS (SEP 2000)

- A. The Lessor may be requested to provide alterations during the term of the lease. Alterations will be ordered by issuance of GSA Form 276, Supplemental Lease Agreement, GSA Form 300, Order for Supplies or Services, or a Tenant Agency-approved form. The two clauses from GSA Form 3517, General Clauses, 552.232-25, Prompt Payment (Deviation FAR 52.232-25), and 552.232-70, Invoice Requirements, apply to orders for alterations. All orders are subject to the terms and conditions of this lease.
- B. Orders may be placed by the 1) Contracting Officer, 2) GSA Buildings Manager, or 3) Tenant Agency officials when specifically authorized to do so by the Contracting Officer. The Contracting Officer will provide the Lessor with a list of Tenant Agency officials authorized to place orders and will specify any limitations on the authority delegated to Tenant Agency officials. The Tenant Agency officials are not authorized to deal with the Lessor on any other matters.
- C. Payments for alterations ordered by the Tenant Agency will be made directly by the Tenant Agency placing the order.

#### 3.4 **ALTERNATE PROPOSALS**

- A. This SFO may specify certain items for which alternate proposals are required. For evaluation and negotiation, the offer shall state:
  - 1. itemized costs for lump sum payment not to be included in the rental rate and
  - 2. a rental rate which includes the costs of these items.
- B. The Offeror shall provide costs for both methods of evaluation on GSA Form 1364, Proposal to Lease Space, in order to be considered for award. GSA may elect the option it deems most favorable.

#### 3.5 **TAX ADJUSTMENT (SEP 2000)**

- A. Real estate taxes, as referred to in this paragraph, are only those taxes which are assessed against the building and/or the land upon which the building is located, without regard to benefit to the property, for the purpose of funding general Government services. Real estate taxes shall not include, without limitation, general and/or special assessments, business improvement district assessments, or any other present or future taxes or governmental charges that are imposed upon the Lessor or assessed against the building and/or the land upon which the building is located.
- B. Base year taxes as referred to in this paragraph are 1) the real estate taxes for the first 12-month period of the lease term coincident with full assessment or 2) may be an amount negotiated by the parties that reflects an agreed upon base for a fully assessed value of the property.
- C. The term "full assessment" as referred to in this paragraph means that the taxing jurisdiction has considered all contemplated improvements to the assessed property in the valuation of the same. Partial assessments for newly constructed projects or for projects under construction, conversion, or renovation will not be used for establishing the Government's base year for taxes.
- D. The Lessor shall furnish the Contracting Officer with copies of all notices which may affect the valuation of said land and buildings for real estate taxes thereon, as well as all notices of a tax credit, all tax bills, and all paid tax receipts, or where tax receipts are not given, other similar evidence of payment acceptable to the Contracting Officer (hereinafter, evidence of payment), and a proper invoice (as described in GSA Form 3517, General Clauses, 552.232-75, Prompt Payment) of the tax adjustment including the calculation thereof, for each year that real estate taxes are incurred during the lease term or any extension thereof. All such documents are due within 10 calendar days of receipt except that the proper invoice and evidence of payment shall be submitted within 60 calendar days after the date the tax payment is due from the Lessor to the taxing authority. FAILURE TO SUBMIT THE PROPER INVOICE AND EVIDENCE OF PAYMENT WITHIN SUCH TIME FRAME SHALL BE A WAIVER OF THE RIGHT TO RECEIVE PAYMENT RESULTING FROM AN INCREASED TAX ADJUSTMENT UNDER THIS PARAGRAPH.
- E. The Government shall 1) make a single annual lump sum payment to the Lessor for its share of any increase in real estate taxes during the lease term over the amount established as the base year taxes or 2) receive a rental credit or lump sum payment for its share of any decreases in real estate taxes during the lease term below the amount established as the base year taxes. The amount of lump sum payment or rental credit shall be based upon evidence of valuation and payment submitted by the Lessor to the Contracting Officer in accordance with subparagraph D.
  - In the event of an increase in taxes over the base year, the Lessor shall submit a proper invoice of the tax adjustment including the calculation thereof together with evidence of payment to the Contracting Officer. THE GOVERNMENT SHALL BE RESPONSIBLE FOR PAYMENT OF ANY TAX INCREASE OVER THE BASE YEAR TAXES ONLY IF THE PROPER INVOICE AND EVIDENCE OF PAYMENT IS SUBMITTED BY THE LESSOR WITHIN 60 CALENDAR DAYS AFTER THE DATE THE TAX PAYMENT IS DUE FROM THE LESSOR TO THE TAXING AUTHORITY. The due date for making payment shall be the 30<sup>th</sup> calendar day after receipt of evidence of payment by the Contracting Officer or the 30<sup>th</sup> calendar day after the anniversary date of the lease, whichever is later. If the lease terminates before the end of a tax year, payment for the tax increase due as a result of this section for the tax year will be prorated based on the number of days that the Government occupied the space. No increase will be paid, due, or owing unless all evidence of valuation and payment has been previously submitted to the Contracting Officer. The Government's payment for its share of real estate taxes shall not include any late charges, interest, or penalties imposed by the taxing authority as a result of the Lessor's delinquency in paying such taxes or charges.

INITIALS: LESSOR & LESSOR

- In the event of a decrease in taxes from the base year, or in the event of any refund or tax deduction, the Lessor shall notify the Contracting Officer in accordance with subparagraph D. The Government shall be entitled to, and shall receive a credit for, the prorata reduction in taxes applicable to the premises encumbered by this lease, regardless of whether the Government has made a tax payment for that year. The Government's share of the credit will be determined in accordance with subparagraph F and shall be taken as a deduction from the rent. Any credit due the Government after the expiration or earlier termination of the lease (including, but not limited to, credits resulting from a decrease in taxes pursuant to a tax credit due the Lessor; a reduction in the tax assessment; or a tax appeal proceeding for a year of the lease, or portion thereof) shall be made by a lump sum payment to the Government or as a rental credit to any succeeding lease as determined by the Contracting Officer. The Lessor shall remit any lump sum payment to the Government within 15 calendar days of payment by the taxing authority to the Lessor's designee. If the credit due to the Government is not paid by the due date, interest shall accrue on the late payment at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978 (United States Code 41 USC 611) that is in effect on the day after the due date. The interest penalty shall accrue daily on the amount of the credit and shall be compounded in 30-day increments inclusive from the first day after the due date through the payment date. The Government shall have the right to pursue the outstanding balance of any tax credit using all such collection methods as are available to the United States to collect debts. Such collection rights shall survive the expiration of this lease.
- F. The Government shall pay its share of tax increases or shall receive its share of any tax decrease based on the ratio of the rentable square feet occupied by the Government to the total rentable square feet in the building or complex (percentage of occupancy). For the purpose of this lease, the Government's percentage of occupancy as of the date hereof is 44 percent based upon an occupancy of 125,902 rentable square feet in a building of 55,397 rentable square feet. This percentage shall be subject to adjustment to take into account additions or reductions of the amount of space as may be contemplated in this lease or amendments hereto. The block and lot/parcel or other identification numbers for the property, building(s), and parking areas(s) occupied under this lease are
- G. The Government may direct the Lessor upon reasonable notice to initiate a tax appeal, or the Government may decide to contest the tax assessment on behalf of the Government and the Lessor or for the Government alone. The Lessor shall furnish to the Government information necessary for appeal of the tax assessment in accordance with the filing requirements of the taxing authority. If the Government decides to contest the tax assessment on its own behalf or on behalf of the Government and the Lessor, the Lessor shall cooperate and use all reasonable efforts including, but not limited to, affirming the accuracy of the documents, executing documents required for any legal proceeding, and taking such other actions as may be required. If the Lessor initiates an appeal on behalf of the Government, the Government and the Lessor will enter into an agreement to establish a method for sharing expenses and tax savings.

#### 3.6 PERCENTAGE OF OCCUPANCY

The percent of the building occupied by the Government, for purposes of tax adjustments, will be established during negotiations.

### 3.7 **OPERATING COSTS (NCR VARIATION (NOV 2001)**

- Beginning with the second year of the lease and each year thereafter, the Government shall pay adjusted rent for changes in costs for cleaning services, supplies, materials, maintenance, trash removal, landscaping, water and sewer charges, heating, electricity, and certain administrative expenses attributable to occupancy. Applicable costs listed on GSA Form 1217, Lessor's Annual Cost Statement, when negotiated and agreed upon, will be used to determine the base operating cost adjustments. The agreed-upon initial operating costs shall be stated on the SF-2 or other lease document.
- (B) The amount of adjustment will be determined by multiplying the base operating costs by the percent change in the revised Consumer Price Index (CPI) for wage earners and clerical workers, U.S. City average, all items figure, (1982-1984 = 100) published by the Bureau of Labor Statistics, U.S. Department of Labor.
- (C) The first percent change will be computed by comparing the index figure published for the month prior to the lease commencement date with the index figure published for the month before the anniversary date of the lease. For example, a lease commencing in June of 2001 would use the index published for May of 2001 and that figure would be compared with the index published for May of 2002 to determine the percent change.
- (D) Each successive adjustment shall use the percent difference between the prior year index figure and the current year index figure for the month before the next anniversary date of the lease. In the example used, the second adjustment would compare the CPI for May of 2002 with that of May of 2003 to determine the percent change. The percent change shall be applied to the escalated operating costs from the previous year. For example, if the initial operating costs were \$10,000 and the initial adjustment calculated under paragraph (C) above were \$250, then the operating costs to be used for the second adjustment calculation would be \$10,250.
- (E) Payment will be by permanently adding 1/12 of the adjustment to the monthly installment of fixed rent. Rental adjustments will be effective on the anniversary date of the lease. Payment of the adjusted rental rate will become due (for purposes of any interest due) on the first workday of the second month following the publication of the CPI for the month prior to the anniversary date (adjustment effective date).
- (F) If the Government exercises an option to renew the lease term annual adjustments will continue in the manner described above.
- (G) Change in base operating costs.

INITIALS: LESSOR &

- (i) If a change in the operating costs occurs for such things as commencement of daytime cleaning or expansion of space (where the expansion space is rented at the same rate as the original space), annual adjustments shall be calculated separately on the increase/decrease in operating costs. However, such adjustment shall be effective only after the increased costs have been in effect for at least one year. Therefore, for expansions not occurring on the anniversary date of the lease, the adjustment shall be due and payable on the anniversary date of the lease following the first anniversary date of the expansion. The first rent adjustment for the increase in base operating costs shall be calculated by comparing the CPI for the month before the effective date of the change in base operating costs (such as the expansion effective date) with the CPI for the month before the lease anniversary date. For subsequent adjustments, the increase in the base operating costs shall be added to the other escalated base operating costs and only one calculation shall be made.
- (ii) In cases where an expansion of leased space occurs and the expansion space is rented at a different rate than the original space, the base operating costs shall be reestablished in the Supplemental Lease Agreement to take the additional space. The new base operating costs shall be a prorated blend of the escalated original base operating costs and the base operating costs for the new space from the GSA Form 1217 for the new space. The CPI's shall continue to be determined as specified in paragraph (D) above, and operating cost rental adjustments shall continue to be made on the anniversary date of the lease.
- (H) In the event of a decrease in the CPI during the occupancy under the lease, the rental amount will be reduced accordingly. The amount of such reduction will be determined in the same manner as increases in the rent provided under this clause.
- The offer shall clearly state whether the rental is firm throughout the term of the lease or if it is subject to annual adjustment of operating costs as indicated above. If operating costs will be subject to adjustment, those costs shall be specified on GSA Form 1364, Proposal to Lease Space, contained elsewhere in this SFO.

#### 3.8 **OPERATING COSTS BASE (SEP 2000)**

The base for the operating costs adjustment will be established during negotiations based upon ANSI/BOMA Office Area square feet.

#### 3.9 RENTABLE SPACE (SEP 2000)

Rentable space is the area for which a tenant is charged rent. It is determined by the building owner and may vary by city or by building within the same city. The rentable space may include a share of building support/common areas such as elevator lobbies, building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The rentable space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts.

# ANSI/BOMA OFFICE AREA SQUARE FEET (NCR VARIATION (AUG 2002))

- A. For the purposes of this SFO, the Government recognizes the American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) international standard (Z65.1-1996) definition for Office Area, which means "the area where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed."
- B. ANSI/BOMA Office Area square feet shall be computed by measuring the area enclosed by the finished surface of the room side of corridors (corridors in place as well as those required by local codes and ordinances to provide an acceptable level of safety and/or to provide access to essential building elements) and other permanent walls, the dominant portion (refer to Z65.1) of building exterior walls, and the center of tenant-separating partitions. Where alcoves, recessed entrances, or similar deviations from the corridor are present, ANSI/BOMA Office Area square feet shall be computed as if the deviation were not present. For purposes of this solicitation, floor common area, including rest rooms, janitors closets, telephone and electrical closets, mechanical rooms ,elevator lobbies, and public or fire safety egress corridors are not included.

### 3.11 **COMMON AREA FACTOR (SEP 2000)**

If applicable, the Offeror shall provide the Common Area Factor (a conversion factor(s) determined by the building owner and applied by the owner to the ANSI/BOMA Office Area square feet to determine the rentable square feet for the offered space).

#### 3.12 **APPURTENANT AREAS**

The right to use appurtenant areas and facilities is included. The Government reserves the right to post Government rules and regulations where the Government leases space.

### 3.13 LIQUIDATED DAMAGES, GSAR 552.270-15 (SEP 1999)

In case of failure on the part of the Lessor to complete the work within the time fixed in the lease contract or letter of award, the Lessor shall pay the Government as fixed and agreed liquidated damages, pursuant to this paragraph, the sum of \_1000\_\_\_ for each and every calendar day that the delivery is delayed beyond the date specified for delivery of all the space ready for occupancy by the Government. This remedy is not exclusive and is in addition to any other remedies which may be available under this lease or at law.

### **VENDING FACILITIES (SEP 2000)** 3.14

 A. Approximately square feet of the ANSI/BOMA Office Area space in the "Amount and Type of Space" paragraph of the SUMMARY section of this SFO will be used for the operation of a vending facility(ies) by the blind under the provisions of

INITIALS: LESSOR & COUT

the Randolph-Sheppard Act (United States Code 20 USC 107 et. seq.). The Government will control the number, kind, and locations of vending facilities and will control and receive income from all automatic vending machines. The Lessor is required to provide necessary utilities and to make related alterations. The cost of the improvements will be negotiated, and payment will be made by the Government either on a lump-sum basis or a rental increase.

B. The Government will assure that the facility(ies) does not compete with other facilities having exclusive rights in the building. The Offeror shall advise the Government if such rights exist.

# 3.15 ADJUSTMENT FOR VACANT PREMISES, GSAR 552.270-16 (VARIATION) (SEP 1999)

- A. If the Government fails to occupy any portion of the leased premises or vacates the premises in whole or in part prior to expiration of the term of the lease, the rental rate will be reduced.
- B. The rate will be reduced by that portion of the costs per ANSI/BOMA Office Area square foot of operating expenses not required to maintain the space. Said reduction shall occur after the Government gives 30 calendar days prior notice to the Lessor and shall continue in effect until the Government occupies the premises or the lease expires or is terminated.

# 3.16 RELOCATION ASSISTANCE ACT (MAR 2002)

- A. If an Offeror proposes an improved site and new construction will result in the displacement of individuals or businesses, the successful Offeror shall be responsible for payment of relocation costs in accordance with the Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970 (P.L. 91-646), as amended, and the implementing regulations at 49 CFR Part 24.
- B. Offerors shall incorporate the cost of such assistance into their shell rental rate.
- C. The successful Offeror shall give GSA the name of the person and agency to be providing the relocation assistance to site tenants. In addition, the successful Offeror must provide background information about the relocation agency and references for which the relocation agent has performed relocation assistance in the past. Depending upon the complexity of the relocation project, Offerors may be required to provide a relocation plan with final proposal revisions.

### 3.17 EVIDENCE OF CAPABILITY TO PERFORM (SEP 2000)

- A. AT THE TIME OF SUBMISSION OF OFFERS, THE OFFEROR SHALL SUBMIT TO THE CONTRACTING OFFICER:
  - Satisfactory evidence of at least a conditional commitment of funds in an amount necessary to prepare the space. Such
    commitments shall be signed by an authorized bank officer and at a minimum shall state: amount of loan; term in years;
    annual percentage rate; and length of loan commitment.
  - 2. The name of the proposed construction contractor, as well as evidence of the contractor's experience, competency, and performance capabilities with construction similar in scope to that which is required herein.
  - The license or certification to practice in the state where the facility is located from the individual(s) and/or firm(s) providing architectural and engineering design services.
  - 4. Compliance with local zoning laws or evidence of variances, if any, approved by the proper local authority.
  - 5. Evidence of ownership or control of site.

R	AF	ΓFR	$\Delta M$	/ARD:

Within \_\_\_5\_\_\_ days after award, the successful Offeror shall provide to the Contracting Officer evidence of:

- 1. A firm commitment of funds in an amount sufficient to perform the work.
- 2. Award of a construction contract for Tenant Improvements with a firm completion date.
- 3. Issuance of a building permit covering construction of the improvements.

# 3.18 CONSTRUCTION SCHEDULE

- A. Within \_10 Calendar \_\_\_\_\_ days after award of the lease contract, the successful Offeror shall submit to the Contracting Officer a tentative construction schedule giving the dates on which the various phases of construction will be completed to coincide with the Government's required occupancy date. Refer to the "Occupancy Date" paragraph in the SUMMARY section of this SFO. The finalized schedule shall be submitted no later than \_\_15\_\_\_\_\_ days after award.
- B. The schedule shall include timing for completion of design and construction milestones including, but not limited to: 1) submittal of preliminary plans and specifications; 2) submittal of other working drawings; 3) issuance of a building permit; 4) completed construction documents; 5) start of construction; 6) completion of principal categories of work; 7) phased completion and availability for occupancy of each portion of the Government-demised area (by floor, block, or other appropriate category); and 8) final construction completion.

# 3.19 CONSTRUCTION SCHEDULE OF TENANT IMPROVEMENTS (SEP 2000)

A. The construction schedule shall commence upon lease award, unless otherwise expressly agreed by the Lessor and Government as stated in the lease. The schedule shall be divided into six tasks for each phase. These are: 1) the generation of the design

INITIAL

LESSOR

intent drawings; 2) the Government's approval of the design intent drawings; 3) the Lessor's generation of the Government's working/construction drawings; 4) the Government's review of the working/construction drawings; 5) the Lessor's construction of the subject leased area; and 6) the Government's acceptance of the Lessor's construction. Each of these tasks is detailed below. References to working days shall be based upon a 5-day work week (Monday through Friday, exclusive of federal holidays). References to "approval" shall mean such approval granted by the Contracting Officer. During the construction schedule, the Government may request regularly scheduled progress meetings and request that the Lessor keep meeting minutes of discussion topics and attendance. During design and construction, the Lessor may discover instances where the Government's directives conflict. In such cases, the Lessor shall immediately notify the Contracting Officer so that the Government may issue a determination as to how to proceed beyond the building shell.

# **B. DESIGN INTENT DRAWINGS:**

- The Lessor shall prepare, at the Lessor's expense, and provide to the Government, for the Government's approval, design intent drawings detailing the Tenant Improvements to be made by the Lessor within the Government-demised area. The Government shall use best efforts to coordinate the provision of such information and details as required by the Lessor's architect to complete such drawings in a timely manner. Design intent drawings, for the purposes of this lease, are defined as fully-dimensioned drawings of the leased space which include enough information to prepare construction drawings and shall consist of: 1) furniture locations, telephone and data outlet types and locations; 2) specifications necessary for calculation of electrical and HVAC loads; and 3) all finish/color/signage selections. Design intent drawings shall be due from the Lessor within \_\_\_\_\_10\_\_\_ working days from award.
- Review. The Government retains the right to review, approve, and request modifications (if necessary) to the Lessor's design intent drawings prior to the Lessor's commencement of working/construction drawings. The Government's review and approval of the drawings is limited as to the drawings' conformance to the specific requirements of the SFO and the agency's needs as they apply to the specific leased space. The Government shall perform all reviews of design intent drawings within \_\_\_\_5\_\_ working days of receipt of such from Lessor. Should the Government require that modifications be made to the Lessor's design intent drawings before approval can be granted, the Government shall state as such in writing to the Lessor, and the Lessor shall have \_\_\_\_5\_\_\_working days to cure all noted defects before returning the design intent drawings to the Government for a subsequent review. Upon approval of the design intent drawings, a notice to proceed shall be transmitted to the Lessor, and the Lessor shall commence working/construction drawings for the space. At the sole discretion of the Government, the Lessor may be required to submit a budget proposal, based on the Tenant Improvements and associated work as shown on the design intent drawings. This budget proposal shall be completed within 10 working days of the Government's request. Delay of receipt of such proposal shall result in a Lessor delay.

# B. DESIGN INTENT DRAWINGS:

The Government shall prepare and provide to the Lessor the Government's approved design intent drawings detailing the Tenant Improvements to be made by the Lessor within the Government-demised area. Design intent drawings, for the purposes of this lease, are defined as fully-dimensioned drawings of the leased space which include enough information to prepare construction drawings and shall consist of: 1) furniture locations, telephone and data outlet types and locations; 2) specifications necessary for calculation of electrical and HVAC loads; and 3) all finish/color/signage selections. Design intent drawings shall be due to the Lessor within 10 working days from award.

# C. WORKING/CONSTRUCTION DRAWINGS:

The Lessor shall prepare, out of the Tenant Improvement Allowance, final working/construction drawings for the improvements illustrated on the Government-approved design intent drawings. The working/construction drawings shall include all mechanical, electrical, plumbing, fire safety, lighting, structural, and architectural improvements scheduled for inclusion into the Government-demised area. Working/construction drawings shall also be annotated with all applicable specifications. The resulting product shall reflect requirements which are substantially the same as that specified by the Government-approved design intent drawings and shall incorporate neither extraneous additions nor deletions of requirements. working/construction drawings shall be due to the Government within working days of the Government's approval of the design intent drawings. Working/construction drawings shall clearly identify 1) Tenant Improvements already in place and 2) the work to be done by the Lessor or others. The Government may also require at the time of submission of working/construction drawings that the Lessor submit a written price proposal along with adequate cost and pricing data for any costs or credits to the Government which are beyond the scope of the original SFO and its attachments. Any work shown on the working/construction drawings which is building shell shall be clearly identified as such.

# D. REVIEW OF WORKING/CONSTRUCTION DRAWINGS:

The Government retains the right to review, and request modifications (if necessary) to, the Lessor's working/construction drawings prior to the Lessor's commencement of interior construction. The Government's review of the working/construction drawings is limited to the working/construction drawings' conformance to the specific requirements of the SFO and to the approved design intent drawings. The Government shall perform all reviews of working/construction drawings within working days of receipt of such from the Lessor. Should the Government require that modifications be made to the Lessor's working/construction drawings, the Government shall state such in writing to the Lessor, and the Lessor shall have working days to cure all noted defects before returning the working/construction drawings to the Government for a subsequent review. Upon complete Government review for conformance of the working/construction drawings to the design intent drawings, A NOTICE TO PROCEED SHALL BE TRANSMITTED TO THE LESSOR, and the Lessor shall obtain the necessary permits and shall commence construction of the space. Notwithstanding the Government's review of the working/construction drawings, the Lessor is solely responsible and liable for the technical accuracy of the working/construction drawings in meeting all requirements and provisions of the lease and the Government-approved design intent drawings.

# E. CONSTRUCTION OF TENANT IMPROVEMENTS:

The Lessor shall construct all Tenant Improvements in accordance with 1) the Government reviewed working/construction drawings and 2) all terms and conditions of the SFO. The Lessor shall complete Tenant Improvements within

INITIALS: LESSOR & GOVT

\_\_\_\_\_5\_\_ working days of receiving the notice to proceed from the Government. The Lessor shall furnish a detailed construction schedule (such as Critical Path Method) to the Government within 5 days of issuance of the notice to proceed. Such schedule shall also indicate the dates available for the Government contractors to install telephone/data lines or equipment. The Government reserves the right to access any space within the building during the conduct of interior construction for the purposes of performing inspections or for installing Government-furnished equipment. The Government shall coordinate with the Lessor the activity of Government contractors in order to minimize conflicts with, and disruption to, other contractors on site. Access shall not be denied to authorized Government officials including, but not limited to, Government contractors, subcontractors, or consultants acting on behalf of the Government with regard to this project.

# F. ACCEPTANCE OF SPACE:

7 days prior to the completion of interior construction, the Lessor shall issue written notice to the Government to inspect the space. The Government shall have 3 working days to inspect and to either accept or reject the subject space.

- Substantially completed space will be accepted by the Government subject to the completion of minor punch list items. Space which is not substantially complete will not be accepted by the Government. Should the Government reject the Lessor's space as not substantially complete as defined herein, the Lessor shall immediately undertake remedial action and when ready shall issue a subsequent notice to inspect to the Government.
- 2. Before the Government will accept space, the Lessor shall provide to the Contracting Officer 1) evidence of the issuance of a building permit incorporating the construction of required improvements and 2) a copy of the Certificate of Occupancy.

# G. RENT COMMENCEMENT:

The rent commencement date (for each increment) shall be the date that space acceptance is made by the Government. Any rental paid by the Government prior to actual occupancy shall be less the cost for services and utilities. In any event, the Government will not be required to accept space and commence rent prior to the original date as indicated until space is 100% complete.

### H. LEASE COMMENCEMENT:

The Government shall issue GSA Form 276, Supplemental Lease Agreement, to establish the lease commencement date after the acceptance of all space. In any case, the lease commencement date shall not be prior to the rent commencement date.

## 3.20 PROGRESS REPORTS (SEP 2000)

## 3.21 CONSTRUCTION INSPECTIONS

- A. Construction inspections will be made periodically by the Contracting Officer and/or designated technical representatives to review compliance with the SFO requirements and the final working drawings.
- B. Periodic reviews, tests, and inspections by the Government are not to be interpreted as resulting in any approval of the Lessor's apparent progress toward meeting the Government's objectives but are intended to discover any information which the Contracting Officer may be able to call to the Lessor's attention to prevent costly misdirection of effort. The Lessor shall remain completely responsible for designing, constructing, operating, and maintaining the building in full accordance with the requirements of this SFO.

# 3.21 REQUIRED PROOF OF AUTHORITY (NCR VARIATION (AUG 2002))

As a condition of lease award, the Government will require one of the following forms of proof of signing authority before the Government executes the lease:

- A. General Partnership Copy of Partnership Agreement
- B. Limited Partnership Copy of Partnership Agreement or copy of current Certificate of Limited Partnership
- C. Corporation Corporate Resolution certified by the Secretary of the Corporation or an Informal Action signed by the Board of Directors. The Resolution or Informal Action must approve the lease and indicate who has authority to sign for the corporation.
- D. Joint Venture Copy of Joint Venture Agreement
- E. Company Copy of formation document indicating who can bind the company

# 3.22 BUSINESS IMPROVEMENT DISTRICTS (B.I.D.) (NCR VARIATION (AUG 2002))

- A. For purposes of this solicitation:
  - (1) "BID" means a Business Improvement District, Special Improvement District, or other specifically defined geographical area within a taxing jurisdiction, organized and registered pursuant to enabling legislation promulgated by a State or local government, within which properties are assessed, charged or taxed solely by virtue of their location within the given area and in support of services or projects located solely within the area.

INITIALS:

LESSOR

GOVI

SFO NO.06-031 09/07/06

- (2) "Building" means the building(s) within which space is provided to the Government under the Lease, together with the land upon which the building is located.
- (3) "Lessor's BID Assessment" means charges, assessments or taxes levied against Lessor and/or a Building, expressed as a fixed sum per Building, solely by virtue of the Building being located within a BID.
- B. The Government agrees, when applicable, to make a single annual lump sum payment to the Lessor for its share of increases in Lessor's BID Assessment over the base year. For purposes of this clause, the base year amount of Lessor's BID Assessment will be determined as the amount in the calendar year in which lease commences.
- C. The Government's share of increases in Lessor's BID Assessment shall be based upon the ratio of the ANSI/BOMA Office Area square feet occupied by the Government to the total ANSI/BOMA Office Area square feet of office and retail space in the Building (percentage of occupancy). Square footage related to parking will not be included in determining the Government's percentage of occupancy. At the Contracting Officer's sole discretion, the Government may pay its share of increases in Lessor's BID Assessment based upon the ratio of the assessed value of the space leased by the Government to the total assessed value of the Building. For purposes of this clause, the Government's percentage of occupancy is stated in the clause of this lease entitled "Tax Adjustment".
- D. The Lessor shall furnish the Government with copies of all bills reflecting Lessor's BID Assessment and evidence of payment of such Lessor's BID Assessment by the Lessor. Evidence of payment must be submitted to the Government within 60 calendar days of the date that payment is due. Failure by Lessor to submit evidence of payment as provided in this paragraph shall act as a waiver of Lessor's right to receive payment under this clause.

# 4.0 GENERAL ARCHITECTURE

# 4.1 QUALITY AND APPEARANCE OF BUILDING EXTERIOR (NCR VARIATION (AUG 2002))

The space offered shall be located in a modern office building with a facade of stone, marble, brick, stainless steel, aluminum, or other permanent materials in good condition acceptable to the Contracting Officer. If not in a new office building, the space offered shall be in a building that has undergone, or will complete by occupancy, first class restoration or adaptive reuse for office space with modern conveniences. If the restoration work is underway or proposed, then architectural plans acceptable to the Contracting Officer shall be submitted as part of the offer. The building shall be compatible with its surroundings. Overall, the building shall project a professional and aesthetically-pleasing appearance including an attractive front and entrance way. The building shall have energy-efficient windows or glass areas consistent with the structural integrity of the building, unless not appropriate for intended use. The facade, downspouts, roof trim, and window casing shall be clean and in good condition.

Should new construction be proposed in response to this solicitation, the face of the building's exterior shall not be less than 50 feet to the protected/defended perimeter (i.e. any potential point of explosion). As an example, this would mean the distance from the building to the curb protected by bollards, planters, or other street furniture. Such potential points of explosion may be, but may not be limited to, such areas that could be accessible by any type of motorized vehicle (i.e. street, alley, sidewalk, driveway, parking lot).

# 4.2 CONSTRUCTION WASTE MANAGEMENT (SEP 2000)

- A. Recycling construction waste means providing all services necessary to furnish construction materials or wastes to organizations which will employ these materials or wastes in the production of new materials. Recycling includes required labor and equipment necessary to separate individual materials from the assemblies of which they form a part.
- B. The Offeror shall submit to the Government a proposal to dispose of or recycle construction waste. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government may permit alternative means of disposal. This requirement shall also apply to subsequent alterations under the lease.
- C. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility:
  - 1. ceiling grid and tile;
  - 2. light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bulbs;
  - 3. duct work and HVAC equipment;
  - 4. wiring and electrical equipment:
  - aluminum and/or steel doors and frames;
  - hardware;
  - 7. drywall;
  - 8. steel studs;
  - 9. carpet, carpet backing, and carpet padding;

INITIALS:

SSOR GOV

SFO NO.06-031 09/07/06

- 10. wood:
- 11. insulation:
- 12. cardboard packaging;
- 13. pallets:
- windows and glazing materials;
- 15. all miscellaneous metals (as in steel support frames for filing equipment); and
- 16. all other finish and construction materials.
- D. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCB's) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with federal and state laws and requirements concerning hazardous waste.
- E. In addition to providing "one-time" removal and recycling of large-scale demolition items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.
- F. Construction materials recycling records shall be maintained and shall be accessible to the Contracting Officer. Records shall include materials recycled or landfilled, quantity, date, and identification of hazardous wastes.

#### 4.3 **EXISTING FIT-OUT, SALVAGED, OR RE-USED BUILDING MATERIAL (SEP 2000)**

- Items and materials existing in the offered space, or to be removed from the offered space during the demolition phase, are eligible for reuse in the construction phase of the project. The reuse of items and materials is preferable to recycling them; however, items considered for reuse shall be in refurbishable condition and shall meet the quality standards set forth by the Government in this SFO. In the absence of definitive quality standards, the Lessor shall ensure that the quality of the item(s) in question shall meet or exceed accepted industry or trade standards for first quality commercial grade applications.
- The Lessor shall submit a reuse plan to the Contracting Officer. The Government will not pay for existing fixtures and other Tenant Improvements accepted in place. However, the Government will reimburse the Lessor, as part of the Tenant Improvement Allowance, the costs to repair or improve such fixtures or improvements identified on the reuse plan and approved by the Contracting Officer.

# **INDOOR AIR QUALITY DURING CONSTRUCTION (SEP 2000)**

- The Lessor shall provide to the Government material safety data sheets (MSDS) upon request for the following products prior to their installation or use: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, and janitorial cleaning products.
- B. The Contracting Officer may eliminate from consideration products with significant quantities of toxic, flammable, corrosive, or carcinogenic material and products with potential for harmful chemical emissions. Materials used often or in large quantities will receive the greatest amount of review.
- C. All MSDS shall comply with Occupational Safety and Health Administration (OSHA) requirements. The Lessor and its agents shall comply with all recommended measures in the MSDS to protect the health and safety of personnel.
- D. To the greatest extent possible, the Lessor shall sequence the installation of finish materials so that materials that are high emitters of volatile organic compounds (VOC) are installed and allowed to cure before installing interior finish materials, especially soft materials that are woven, fibrous, or porous in nature, that may adsorb contaminants and release them over time.
- E. Where demolition or construction work occurs adjacent to occupied space, the Lessor shall erect appropriate barriers (noise, dust, odor, etc.) and take necessary steps to minimize interference with the occupants. This includes maintaining acceptable temperature, humidity, and ventilation in the occupied areas during window removal, window replacement, or similar types of work.
- F. A final flush-out period of 48 hours to 72 hours shall be provided before occupancy. The Lessor shall ventilate with 100 percent outside air at the recommended air change rate during installation of materials and finishes. Refer to the latest edition of American Society of Heating, Refrigerating, and Air Conditioning Engineers, Inc. ANSI/(ASHRAE) Standard 62, Ventilation for Acceptable Indoor Air Quality. If outside air would cause unacceptable inside temperature levels, humidity levels, and/or air quality, an alternate ventilation plan may be submitted to the Contracting Officer for approval.

### 4.5 WORK PERFORMANCE (SEP 2000)

All work in performance of this lease shall be done by skilled workers or mechanics and shall be acceptable to the Contracting Officer. The Contracting Officer retains the right to reject the Lessor's workers 1) if such are either unlicensed, unskilled, or otherwise incompetent or 2) if such have demonstrated a history of either untimely or otherwise unacceptable performance in connection with work carried out in conjunction with either this contract or other Government or private contracts.

INITIALS: LESSOR & COVIT

#### 4.6 **BUILDING SYSTEMS (JAN 1997)**

Whenever requested, the Lessor shall furnish at no cost to GSA a report by a registered professional engineer(s) showing that the building and its systems as designed and constructed will satisfy the requirements of this lease.

#### 4.7 SPACE EFFICIENCY (SEP 2000)

The design of the space offered shall be conducive to efficient layout and good utilization as determined by the Government at its sole discretion.

#### 4.8 CAD AS-BUILT FLOOR PLANS (NCR VARIATION (AUG 2002))

- Computer-Aided Design (CAD) files of as-built floor plans showing the space under lease, as well as corridors, stairways, and core areas, shall be provided to the Contracting Officer at Lessor's cost and the Government shall be entitled to a thirty (30) day inspection period within which to evaluate the quality of the plans. In the event it is determined within the thirty (30) day inspection period that the plans are defective, the Lessor shall provide another set of plans to replace the defective set. After acceptance of the plans, any additional plans will be at the cost of the Government. The plans shall have been generated by a CAD program which is compatible with the latest release of AutoCAD. The required file extension is .DWG. Clean and purged files shall be submitted on 3-1/2-inch double-sided, high density diskettes, or on CD-ROM. They shall be labeled with building name, address, list of drawing(s), date of the drawing(s), and Lessor's architect and phone number and conform to "PBS Standards for CAD Deliverables" (OCT 2001) which are available by request or on the web at http://www.gsa.gov/attachments/GSA POLICIES/extpol/CADdeliverables 6.pdf. The Lessor's operator shall demonstrate the submission on GSA equipment, if requested by the Contracting Officer.
- The Lessor shall be responsible to maintain CAD as-built floor plans at the tenant's expense with each improvement project, which occurs in the Government's space during occupancy. At the time of each update, the Lessor will be responsible to validate all measurements and construction features of the space. In the event that the tenant has made buildout improvements to the space without the Lessor's knowledge or consent, the Government will be responsible for the fair and reasonable design fees to update the as-built drawings.

#### 4.9 FLOORS AND FLOOR LOAD (SEP 2000)

All adjoining floor areas shall be 1) of a common level not varying more than 1/4 inch over a 10-foot, 0-inch horizontal run in accordance with the American Concrete Institute standards, 2) non-slip, and 3) acceptable to the Contracting Officer. Underfloor surfaces shall be smooth and level. Office areas shall have a minimum live load capacity of 50 pounds per ANSI/BOMA Office Area square foot plus 20 pounds per ANSI/BOMA Office Area square foot for moveable partitions. Storage areas shall have a minimum live load capacity of 100 pounds per ANSI/BOMA Office Area square foot including moveable partitions. A report showing the floor load capacity, at no cost to the Government, by a registered professional engineer may be required. Calculations and structural drawings may also be required.

# **EXITS AND ACCESS (SEP 1991)**

Vestibules shall be provided at public entrances and exits wherever weather conditions and heat loss are important factors for consideration. In the event of negative air pressure conditions, provisions shall be made for equalizing air pressure.

#### 4.11 WINDOWS (NCR VARIATION (AUG 2002))

- A. Office space must have "new" and modern, or "refurbished," windows acceptable to the Contracting Officer in each exterior bay. All windows shall be weather-tight. Air infiltration in exterior glazing systems must be no greater than .20 cfm/linear foot of sash perimeter, per ASTM E 783, at a static pressure of 6.24 psf. Windows shall have a fixed sash.
- B. Operable windows that open shall be equipped with locks. Off-street, ground level windows and those accessible from fire escapes, adjacent roofs, and other structures that can be opened shall be fitted with a sturdy locking device.

# 4.12


The building, leased space, and areas serving the leased space shall be accessible to persons with disabilities in accordance with both the ADAAG (36 CFR Part 1191, App. A) and the UFAS (41 CFR Part 101-19.6, App. A). Where standards conflict, the more stringent shall apply.

### **LANDSCAPING (SEP 2000)** 4.13

- A. Where conditions permit, the site shall be landscaped for low maintenance and water conservation with plants that are either native or well-adapted to local growing conditions.
- B. Landscape management practices shall prevent pollution by:
  - 1. employing practices which avoid or minimize the need for fertilizers and pesticides;
  - 2. prohibiting the use of the 2,4-Dichlorophenoxyacetic Acid (2,4-D) herbicide and organophosphates; and
  - 3 composting/recycling all yard waste.

INITIALS: LESSOR & LOV'T

SFO NO.06-031 09/07/06



D. The Contracting Officer shall approve the landscaping to be provided.

# 5.0 ARCHITECTURAL FINISHES

# 5.1 RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (SEP 2000)

- A. The Lessor shall comply to the extent feasible with the Resource Conservation and Recovery Act (RCRA), Section 6002, 1976. The Lessor shall use recycled content products as indicated in this SFO and as designated by the U.S. Environmental Protection Agency (EPA) in the Comprehensive Procurement Guidelines (CPG), 40 CFR Part 247, and its accompanying Recovered Materials Advisory Notice (RMAN). The CPG lists the designated recycled content products. EPA also provides recommended levels of recycled content for these products. The list of designated products, EPA's recommendations, and lists of manufacturers and suppliers of the products can be found at the <a href="https://www.epa.gov/cpg/products.htm">www.epa.gov/cpg/products.htm</a> web site.
- B. The Offeror, if unable to comply with both the CPG and RMAN lists, shall submit a request for waiver for each material to the Contracting Officer with initial offers. The request for waiver shall be based on the following criteria:
  - 1. the cost of the recommended product is unreasonable;
  - 2. inadequate competition exists;
  - 3. items are not available within a reasonable period of time; and
  - 4. items do not meet the SFO's performance standards.

# 5.2 ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS (SEP 2000)

- A. The Lessor shall use environmentally preferable products and materials where economically feasible. Environmentally preferable products have a lesser or reduced effect on human health and the environment when compared to other products and services that serve the same purpose.
- B. Refer to EPA's environmentally preferable products web site, www.epa.gov/opptintr/epp. In general, environmentally preferable products and materials do one or more of the following:
  - 1. contain recycled material, are biobased, or have other positive environmental attributes;
  - 2. minimize the consumption of resources, energy, or water;
  - 3. prevent the creation of solid waste, air pollution, or water pollution; and
  - 4. promote the use of non-toxic substances and avoid toxic materials or processes.

5.3 I	LAYOUT	AND	FINISHES
-------	--------	-----	----------

			be provided with				request for	
Contracting	Officer. GSA	shall deliver	layout drawings	and necessary	finish selections	to	the Lessor	within3
Calendar	days after	award or after r	eceipt of plans and	samples, whiche	ver is later.			

B. All building finishes shall be for first class, modern space.

## 5.4 LAYOUT, FINISHES, AND COLORBOARDS (NCR VARIATION (AUG 2002))

A. All building finishes shall be for first class, modern space.

The Lessor shall consult with the Contracting Officer prior to developing a minimum of5 color boards to include
coordinated samples of finishes for all interior elements such as paint, wall coverings, base coving, carpet, window treatments,
laminates, and vinyl flooring. All samples provided shall be in compliance with specifications set forth elsewhere in this SFO.
Required color boards shall be provided within5 working days of the request for such by the Contracting Officer. The
color boards shall be approved by GSA prior to installation. Upon review with the Tenant Agency(ies), a selection of ONE color
board shall be made within3 working days, and unless otherwise specified prior to lease award, the Offeror may
assume that ONE color board will be accepted for all finishes in the entire space under lease. No substitutes may be made by the
Lessor after the color board is selected.

C. Samples of the building's common area finishes (elevator lobbies, common corridors, rest rooms, etc.) may be required by the Government as a component of the Lessor's offer. Additionally, Lessor is required to submit samples (five sets) of all finishes to be used for the Government demised area on a coordinated finish board.

## 5.5 WOOD PRODUCTS (SEP 2000)

SFO NO.06-031 09/07/06

A. For all new installations of wood products, the Lessor is encouraged to use independently certified forest products. For information on certification and certified wood products, refer to the Forest Stewardship Council United States web site (www.fscus.org/) or the Certified Forest Products Council web site (www.certifiedwood.org/).

26

INITIALS: LESSOR & GOV'T

- B. New installations of wood products used under this contract shall not contain wood from endangered wood species, as listed by the Convention on International Trade in Endangered Species. The list of species can be found at the following web site: www.certifiedwood.org/Resources/CITES/CITESContent.html.
- C. Particle board, strawboard, and plywood materials shall comply with Department of Housing and Urban Development (HUD) standards for formaldehyde emission controls. Plywood materials shall not emit formaldehyde in excess of 0.2 parts per million (ppm), and particleboard materials shall not emit formaldehyde in excess of 0.3 ppm.

#### **ADHESIVES AND SEALANTS (SEP 2000)** 5.6

All adhesives employed on this project (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall be those with the lowest possible VOC content below 20 grams per liter and which meet the requirements of the manufacturer of the products adhered or involved. The Lessor shall use adhesives and sealants with no formaldehyde or heavy metals.

#### 5.7 INSULATION: THERMAL, ACOUSTIC, AND HVAC (SEP 2000)

- A. All insulation products shall contain recovered materials as required by EPA's CPG and related recycled content recommendations.
- No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFC's), nor shall CFC's be used in the installation of the product.
- C. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.
- D. Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578-91.

#### **CEILINGS (SEP 2000)** 5.8

- inches and no more than 12 feet, 0 inches measured from floor to the A. Ceilings shall be at least \_ feet, \_ 6 lowest obstruction. Areas with raised flooring shall maintain these ceiling height limitations above the finished raised flooring. Bulkheads and hanging or surface-mounted light fixtures which impede traffic ways shall be avoided. Ceilings shall be uniform in color and appearance throughout the leased space, with no obvious damage to tiles or grid.
- B. Ceilings shall have a minimum noise reduction coefficient (NRC) of 0.60 throughout the Government-demised area.
- C. Prior to closing the ceiling, the Lessor shall coordinate with the Government for the installation of any items above the ceiling.
- D. Should the ceiling be installed in the Government-demised area prior to the Tenant Improvements, then the Lessor shall be responsible for all costs in regard to the disassembly, storage during alterations, and subsequent re-assembly of any of the ceiling components which may be required to complete the Tenant Improvements. The Lessor shall also bear the risk for any damage to the ceiling or any components thereof during the alterations.
- E. Ceilings shall be a flat plane in each room and shall be suspended with ample light fixtures and finished as follows unless an alternate equivalent is pre-approved by the Contracting Officer:
  - 1. Restrooms. Plaster or pointed and taped gypsum board.
  - 2 Offices and Conference Rooms. Mineral and acoustical tile or lay in panels with textured or patterned surface and tegular edges or an equivalent pre-approved by the Contracting Officer. Tiles or panels shall contain recycled content.
  - 3. Corridors and Eating/Galley Areas. Plaster or pointed and taped gypsum board or mineral acoustical tile.

### **WALL COVERINGS (SEP 2000)** 5.9

# A. BUILDING SHELL:

- Physical Requirements.
  - Prior to occupancy, all restrooms within the building common areas of Government-occupied floors shall have 1) ceramic tile in splash areas and 2) vinyl wall covering not less than 13 ounces per square yard as specified in Federal Specification (FS) CCC-W-408C on remaining wall areas or an equivalent pre-approved by the Contracting Officer.
  - Prior to occupancy, all elevator areas which access the Government-demised area and hallways accessing the Government-demised area shall be covered with vinyl wall coverings not less than 22 ounces per square yard as specified in FS CCC-W-408C or an equivalent pre-approved by the Contracting Officer.
- Replacement. All wall covering shall be maintained in "like new" condition for the life of the lease. Wall covering shall be 2. replaced or repaired at the Lessor's expense any time during the Government's occupancy if it is torn, peeling or permanently stained; the ceramic tile in the restrooms shall be replaced or repaired if it is loose, chipped, broken, or permanently discolored. All repair and replacement work shall be done after working hours.

INITIALS: LESSOR & GOV'T

# **B. TENANT IMPROVEMENT INFORMATION:**

- In the event the Government chooses to install wall covering as part of the Tenant Improvement Allowance, the minimum standard is established as vinyl or polyolefin commercial wall covering weighing not less that 13 ounces per square yard as specified in FS CCC-W-408C or equivalent. The finish shall be pre-approved by the Contracting Officer.
- 2 All wall covering in the Government-demised area shall be maintained in "like new" condition for the life of the lease. Repair or replacement of wall covering shall be at the Lessor's expense and shall include the moving and returning of furnishings, (except where wall covering has been damaged due to the negligence of the Government), any time during the occupancy by the Government if it is torn, peeling, or permanently stained. All repair and replacement work shall be done after working

C.	SAMP	I ES
<b>U</b> .	SKIVIE	ᄕᄄᄓ

The Lessor shall provide at least \_\_\_\_3\_\_\_ samples of each type of wall covering to be installed for selection by the Contracting Officer.

#### 5.10 **PAINTING (SEP 2000)**

# A. BUILDING SHELL

- The Lessor shall bear the expense for all painting associated with the building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Government-demised area shall be spackled and prime painted with low VOC primer. If any building shell areas are already painted prior to Tenant Improvements, then the Lessor shall repaint, at the Lessor's expense, as necessary during Tenant Improvements.
- 2. Public areas shall be painted at least every 3 years.

# B. TENANT IMPROVEMENT INFORMATION:

- Prior to occupancy, all surfaces within the Government-demised area which are designated by GSA for painting shall be newly finished in colors acceptable to GSA.
- Where feasible, reprocessed or consolidated latex paint with zero or low VOC shall be used in accordance with EPA's CPG 2 on all painted surfaces. The type of paint shall be acceptable to the Contracting Officer. The Lessor shall follow the manufacturer's recommendations for the application and maintenance of all paint products.
- Painted surfaces shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if it is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this SFO.
- 4. If the Government desires cyclical repainting during the term of the lease, the cost will be borne by the Tenant Agency.

#### 5.11 **DOORS: EXTERIOR (SEP 2000)**

# A. BUILDING SHELL

- Exterior doors shall be provided at the Lessor's expense unless explicitly requested by the Government in addition to those provided by the Lessor. Exterior doors shall be weather-tight and shall open outward. Hinges, pivots, and pins shall be installed in a manner which prevents removal when the door is closed and locked.
- These doors shall have a minimum clear opening of 32" wide x 80" high (per leaf). Doors shall be heavy-duty, flush, 1) hollow steel construction, 2) solid-core wood, or 3) insulated tempered glass. As a minimum requirement, hollow steel doors shall be fully insulated, flush, #16-gauge hollow steel. Solid-core wood doors and hollow steel doors shall be at least 1-3/4 inches thick. Door assemblies shall be of durable finish and shall have an aesthetically-pleasing appearance acceptable to the Contracting Officer. The opening dimensions and operations shall conform to the governing building, fire safety, accessibility for the disabled, and energy codes and/or requirements.

### 5.12 **DOORS: SUITE ENTRY (SEP 2000)**

# **TENANT IMPROVEMENT INFORMATION:**

Suite entry doors shall be provided as part of the Tenant Improvements at the Government's expense and shall have a minimum clear opening of 32" wide x 84" high (per leaf). Doors shall meet the requirements of being a flush, solid-core, 1-3/4-inch thick, wood door with a natural wood veneer face or an equivalent pre-approved by the Contracting Officer. Hollow core wood doors are not acceptable. They shall be operable by a single effort and shall be in accordance with National Building Code requirements. Doors shall be installed in a metal frame assembly, finished with a semi-gloss oil based paint finish.

### 5.13 **DOORS: INTERIOR (SEP 2000)**

# **TENANT IMPROVEMENT INFORMATION:**

Doors within the Government-demised area shall be provided as part of the Tenant Improvements at the Government's expense and shall have a minimum clear opening of 32" wide x 80" high. Doors shall meet the requirements of being a flush, solid-core, wood door with a natural wood veneer face or an equivalent pre-approved by the Contracting Officer. Hollow core wood doors are not acceptable. They shall be operable with a single effort and shall be in accordance with National Building Code requirements. Doors shall be installed in a metal frame assembly, primed and finished with a low VOC semi-gloss oil based paint with no formaldehyde.

INITIALS: LESSOR & DOUT



# A. BUILDING SHELL:

Doors shall have door handles or door pulls with heavyweight hinges. All doors shall have corresponding doorstops (wall- or floor-mounted) and silencers. All public use doors and toilet room doors shall be equipped with kick plates. Exterior doors and all common area doors shall have automatic door closers. All building exterior doors shall have locking devices installed to reasonably deter unauthorized entry. Properly rated and labeled fire door assemblies shall be installed on all fire egress doors.

# B. TENANT IMPROVEMENT INFORMATION:

Doors shall have door handles or door pulls with heavy-weight hinges. All doors shall have corresponding door stops (wall- or floor-mounted) and silencers. All door entrances leading into the Government-demised area from public corridors and exterior doors shall have automatic door closers. Doors designated by the Government shall be equipped with 5-pin, tumbler cylinder locks, and strike plates. All locks shall be master keyed. The Government shall be furnished with at least two master keys for each lock. Any exterior entrance shall have a high security lock, with appropriate key control procedures, as determined by Government specifications. Hinge pins and hasps shall be secured against unauthorized removal by using spot welds or peened mounting bolts. The exterior side of the door shall have a lock guard or astragal to prevent jimmying of the latch hardware. Doors used for egress only shall not have any operable exterior hardware. All security-locking arrangements on doors used for egress shall comply with requirements of NFPA 101.

#### **DOORS: IDENTIFICATION (SEP 2000)** 5.15

# A. BUILDING SHELL:

All signage required in common areas unrelated to tenant identification shall be provided and installed at the Lessor's expense.

# B. TENANT IMPROVEMENT INFORMATION:

Door identification shall be installed in approved locations adjacent to office entrances as part of the Tenant Improvement Allowance. The form of door identification shall be approved by the Contracting Officer.

# **PARTITIONS: GENERAL (SEP 2000)**

# A. BUILDING SHELL:

Partitions in public areas shall be marble, granite, hardwood, sheetrock covered with durable vinyl wall covering, or an equivalent pre-approved by the Contracting Officer.

#### 5.17 **PARTITIONS: PERMANENT (SEP 2000)**

# A. BUILDING SHELL:

Permanent partitions shall extend from the structural floor slab to the structural ceiling slab. They shall be provided by the Lessor at the Lessor's expense as necessary to surround the Government-demised area, stairs, corridors, elevator shafts, toilet rooms, all columns, and janitor closets. They shall have a flame spread rating of 25 or less and a smoke development rating of 50 or less (ASTM E-84). Stairs, elevators, and other floor openings shall be enclosed by partitions and shall have the fire resistance required by National Fire Protection Association (NFPA) Standard 101, Life Safety Code.

# PARTITIONS: SUBDIVIDING (SEP 2000)

# A. BUILDING SHELL:

Any demolition of existing improvements which is necessary to satisfy the Government's layout shall be done at the Lessor's expense.

# B. TENANT IMPROVEMENT INFORMATION:

- Office subdividing partitions shall comply with applicable building codes and local requirements and shall be provided at the expense of the Government. Partitioning shall extend from the finished floor to the finished ceiling and shall be designed to provide a sound transmission class (STC) of 37. Partitioning shall be installed by the Lessor at locations to be determined by the Government as identified in the design intent drawings. They shall have a flame spread rating of 25 or less and a smoke development rating of 50 or less (ASTM E-84).
- 2 HVAC shall be rebalanced and lighting repositioned, as appropriate, after installation of partitions.
- 3. Partitioning requirements may be met with existing partitions if they meet the Government's standards and layout requirements.

### 5.19 FLOOR COVERING AND PERIMETERS (SEP 2000)

# A. BUILDING SHELL

- Exposed interior floors in primary entrances and lobbies shall be marble, granite, terrazzo, or an equivalent pre-approved by the Contracting Officer. Exposed interior floors in secondary entrances, elevator lobbies, and primary interior corridors shall be high-grade carpet, marble, granite, terrazzo, durable vinyl composite tile, or an equivalent pre-approved by the Contracting Officer. Resilient flooring, or an equivalent pre-approved by the Contracting Officer, shall be used in telecommunications rooms. Floor perimeters at partitions shall have wood, rubber, vinyl, marble, carpet base, or an equivalent pre-approved by the Contracting Officer.
- Terrazzo, unglazed ceramic tile, recycled glass tile, and/or quarry tile shall be used in all toilet and service areas unless another covering is pre-approved by the Contracting Officer.

INITIALS: LESSOR & 2



- Except when damaged by the Government, the Lessor shall repair or replace carpet at the Lessor's expense at any time during the lease term when:
  - a. backing or underlayment is exposed;
  - h there are noticeable variations in surface color or texture; or
  - tears and tripping hazards are present.
- Repair or replacement shall include the moving and returning of furnishings. Work shall be performed after normal working hours as defined elsewhere in this SFO.

# C. RESILIENT FLOORING - REPAIR OR REPLACEMENT:

- Except when damaged by the Government, the Lessor shall repair or replace resilient flooring at the Lessor's expense at any time during the lease term when:
  - it has curls, upturned edges, or other noticeable variations in texture.
- 2. Repair or replacement shall include the moving and returning of furnishings. Work shall be performed after normal working hours as defined elsewhere in this SFO.

# D. TENANT IMPROVEMENT INFORMATION:

- Floor covering shall be either carpet or resilient flooring, as specified in the Government's design intent drawings. Floor perimeters at partitions shall have wood, rubber, vinyl, carpet base, or an equivalent pre-approved by the Contracting Officer.
- The use of existing carpet may be approved by the Contracting Officer; however, existing carpet shall be repaired, stretched, and cleaned before occupancy and shall meet the static buildup requirement for new carpet.
- 3. If the Government requires restrooms and/or shower rooms in the Government-demised area, floor covering shall be terrazzo, unglazed ceramic tile, and/or quarry tile.

## E. INSTALLATION:

Floor covering shall be installed in accordance with manufacturing instructions to lay smoothly and evenly.

# F. SAMPLES:

When floor covering is to be newly installed or changed, the Lessor shall provide the Government with a minimum of different color samples of each type of floor covering. The sample and color shall be approved by GSA prior to installation. No substitutes may be made by the Lessor after sample selection.


#### 5.20 **CARPET: BROADLOOM (SEP 2000)**

- A. Any carpet to be newly installed shall meet the following specifications:
  - Pile Yarn Content. Pile yarn content shall be staple filament or continuous filament branded by a fiber producer (e.g., Allied, DuPont, Monsanto, BASF, Talisman Mills, woolblend), soil-hiding nylon, or wool nylon blends or polyethylene terephthalate (PET) resin.
  - 2. Environmental Requirements. The Lessor shall use carpet that meets the "Green Label" requirements of the Carpet and Rug Institute unless an exception is granted by the Contracting Officer.
  - 3. Carpet Pile Construction. Carpet pile construction shall be level loop, textured loop, level cut pile, or level cut/uncut pile.
  - 4. Pile Weight. Pile weight shall be a minimum of 26 ounces per square yard for level-loop or textured-loop construction. Pile weight shall be a minimum weight of 32 ounces per square yard for level-cut/uncut construction.
  - 5. Secondary Back. The secondary back shall be jute or synthetic fiber for glue-down installation.
  - Density. The density shall be 100 percent nylon (loop and cut pile) with a minimum of 4,000; other fibers, including blends 6. and combinations with a minimum of 4.500.
  - 7. Pile Height. The maximum pile height shall be 1/2 inch (13 mm). Exposed edges of carpet shall be fastened to floor surfaces and shall have trim along the entire length of the exposed edge.

### **CARPET TILE (SEP 2000)** 5.21

- A. Any carpet to be newly installed shall meet the following specifications:
  - 1. Pile Yarn Content. Pile yarn content shall be staple filament or continuous filament branded by a fiber producer (e.g., Allied, DuPont, Monsanto, BASF), soil-hiding nylon or polyethylene terephthalate (PET) resin.

INITIALS: LESSOR & GOV'T



- 3. Carpet Pile Construction. Carpet pile construction shall be tufted level loop, level cut pile, or level cut/uncut pile.
- 4. Pile Weight. Pile weight shall be a minimum of 26 ounces per square yard for level loop and cut pile. Pile weight shall be a minimum of 32 ounces per square yard for plush and twist.
- Secondary Back. The secondary back shall be polyvinyl chloride, ethylene vinyl acetate, polyurethane, polyethylene, bitumen, or olefinic hardback reinforced with fiberglass.
- 6. Total Weight. Total weight shall be a minimum of 130 ounces per square yard.
- 7. Density. The density shall be 100 percent nylon (loop and cut pile) with a minimum of 4,000; other fibers, including blends and combinations with a minimum of 4,500.
- 8. Pile Height. The minimum pile height shall be 1/8 inch. The combined thickness of the pile, cushion, and backing height shall not exceed 1/2 inch (13 mm).
- 9. Static Buildup. Static buildup shall be a maximum of 3.5 kilovolt, when tested in accordance with AATCC-134.
- 10. Carpet Construction. Carpet construction shall be a minimum of 64 tufts per square inch.
- 11. Integrated Adhesive. If Carpet Tile is specified with an Integrated "peel & stick" adhesive, the adhesive is to be low VOC type as described in SFO paragraph 5.6 Adhesives and Sealants.

## 5.22 ACOUSTICAL REQUIREMENTS (SEP 2000)

# A. BUILDING SHELL:

- 1. Reverberation Control. Ceilings in carpeted space shall have a noise reduction coefficient (NRC) of not less than 0.55 in accordance with ASTM C-423. Ceilings in offices, conference rooms, and corridors having resilient flooring shall have an NRC of not less than 0.65.
- 2. Ambient Noise Control. Ambient noise from mechanical equipment shall not exceed noise criteria curve (NC) 35 in accordance with the ASHRAE Handbook of Fundamentals in offices and conference rooms; NC 40 in corridors, cafeterias, lobbies, and toilets; NC 50 in other spaces.
- 3. Noise Isolation. Rooms separated from adjacent spaces by ceiling-high partitions (not including doors) shall not be less than the following noise isolation class (NIC) standards when tested in accordance with ASTM E-336:

a. Conference rooms

NIC 40

b. Offices

NIC 35

## 4. Testing.

- a. The Contracting Officer may require, at no cost to the Government, test reports by a qualified acoustical consultant showing that acoustical requirements have been met.
- The requirements of this paragraph shall take precedence over any additional specifications in this SFO if there is a conflict.

# 5.23 WINDOW COVERINGS (SEP 2000)

# A. TENANT IMPROVEMENT INFÓRMATION:

- 1. Window Blinds. All exterior windows shall be equipped with window blinds in new or like new condition, which shall be provided as part of the Tenant Improvement Allowance. The blinds may be aluminum or plastic vertical blinds or horizontal blinds with aluminum slats of 1-inch width or less or an equivalent pre-approved by the Contracting Officer. The window blinds shall have non-corroding mechanisms and synthetic tapes. Color selection will be made by the Contracting Officer.
- 2. Draperies. If draperies are required, the following minimum specifications shall apply:
  - a. Fabrics shall be lined with either white or off-white plain lining fabric suited to the drapery fabric weight. Draperies shall be either floor-, apron-, or sill-length, as specified by the Government, and shall be wide enough to cover window and trim. Draperies shall be hung with drapery hooks on well-anchored heavy duty traverse rods. Traverse rods shall draw from either the center, right, or left side.

INITIALS:

LESSOR

SOVIT



- i. fullness of 100 percent, including overlap, side hems, and necessary returns;
- ii. double headings of 4 inches turned over a 4-inch permanently finished stiffener;
- iii. doubled side hems of 1-1/2 inches; 4-inch doubled and blind stitched bottom hems;
- iv. three-fold pinch pleats;
- v. safety stitched intermediate seams;
- vi. matched patterns;
- vii. tacked corners; and
- viii. no raw edges or exposed seams.
- c. Use of existing draperies must be approved by the Contracting Officer.
- 3. Samples. A minimum of \_\_\_\_3\_\_\_ patterns and colors shall be made available to the Government for selection; shading of sample fabric shall not vary markedly from that of the final product.

# 5.24 BUILDING DIRECTORY (SEP 2000)

# A. BUILDING SHELL:

A tamper-proof directory with lock shall be provided in the building lobby listing the Government agency(ies). It must be acceptable to the Contracting Officer.

# 5.25 FLAG POLE (SEP 2000)

# A. BUILDING SHELL:

If the Government is the sole occupant of the building, a flag pole shall be provided at a location to be approved by the Contracting Officer. The flag will be provided by the Government. This requirement may be waived if determined inappropriate by

# 6.0 MECHANICAL, ELECTRICAL, PLUMBING

## 6.1 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (SEP 2000)

### A. BUILDING SHELL:

The Lessor shall provide and operate all building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures. Mains, lines, and meters for utilities shall be provided by the Lessor. Exposed ducts, piping, and conduits are not permitted in office space.

# 6.2 ENERGY COST SAVINGS (SEP 2000)

- A. The Offeror is encouraged to use 1) Energy Savings Performance Contracts (ESPC) or 2) utility agreements to achieve, maintain, and/or exceed the ENERGY STAR Benchmark Score of 75. The Offeror is encouraged to include shared savings in the offer as a result of energy upgrades where applicable. The ENERGY STAR Online Benchmark Tool can be found at the www.epa.gov/energystar web site.
- B. All new construction shall achieve an ENERGY STAR Building Label within 1 year after reaching 95 percent occupancy and will continue to retain the ENERGY STAR Building Label if the level of performance is maintained.
- C. The Offeror may obtain a list of energy service companies qualified under the Energy Policy Act to perform ESPC, as well as additional information on cost-effective energy efficiency, renewables, and water conservation. For the ESPC qualified list, refer to the www.eren.doe.gov/femp web site, or call the FEMP Help Desk at 1-800-566-2877.

# 6.3 DRINKING FOUNTAINS (SEP 2000)

# A. <u>BUILDING SHELL</u>:

The Lessor shall provide, on each floor of office space, a minimum of one chilled drinking fountain within every 150 feet, 0 inches of travel distance.

## 6.4 TOILET ROOMS (SEP 2000)

# A. BUILDING SHELL:

- Separate toilet facilities for men and women shall be provided on each floor occupied by the Government in the building. The facilities shall be located so that employees will not be required to travel more than 200 feet, 0 inches on one floor to reach the toilets. Each toilet room shall have sufficient water closets enclosed with modern stall partitions and doors, urinals (in men's room), and hot (set in accordance with applicable building codes) and cold water. Water closets and urinals shall not be visible when the exterior door is open.
- Each main toilet room shall contain the following equipment:
  - a. a mirror above the lavatory:

INITIALS: \_\_\_\_\_ & \_\_\_

\_ & 20VT

SFO NO.06-031 09/07/06

- b. a toilet paper dispenser in each water closet stall, that will hold at least two rolls and allow easy, unrestricted
- C. a coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories;
- d. at least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories;
- a coin-operated sanitary napkin dispenser in women's toilet rooms with a waste receptacle for each water closet stall; e.
- f. ceramic tile, recycled glass tile, or comparable wainscot from the floor to a minimum height of 4 feet, 6 inches;
- a disposable toilet seat cover dispenser; and g.
- h. a counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground fault interrupt-type convenience outlet located adjacent to the counter
- B. If newly installed, toilet partitions shall be made from recovered materials as listed in EPA's CPG.

### 6.5 **TOILET ROOMS: FIXTURE SCHEDULE (SEP 2000)**

A. BUILDING SHELL:

- The toilet fixture schedule specified below shall be applied to each full floor based on one person for each 135 ANSI/BOMA Office Area square feet of office space in a ratio of \_\_\_50\_\_\_\_ percent men and \_\_\_50\_\_\_ percent women.
- 2. Refer to the schedule separately for each sex.

NUMBER OF MEN*/WOMEN			WATER CLOSETS	LAVATORIES
1			1	1
16	-	35	2	2
36	-	55	3	3
56	-	60	4	3
61	-	80	4	4
81	-	90	5	4
91	-	110	5	5
111	-	125	6	5
126	-	150	6	**
	> 150	)	***	

In men's facilities, urinals may be substituted for 1/3 of the water closets specified.

#### 3. For new installations:

- Water closets shall not use more than 1.6 gallons per flush. a.
- b. Urinals shall not use more than 1.0 gallons per flush.
- Faucets shall not use more than 2.5 gallons per minute at a flowing water pressure of 80 pounds per square inch.

#### 6.6 **JANITOR CLOSETS (SEP 2000)**

A. BUILDING SHELL

Janitor closets with service sink, hot and cold water, and ample storage for cleaning equipment, materials, and supplies shall be provided on all floors. Each janitor closet door shall be fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch

INITIALS: 2 & 20VIT

SFO NO.06-031 09/07/06

33

Add one lavatory for each 45 additional employees over 125.

<sup>\*\*\*</sup> Add one water closet for each 40 additional employees over 150.

# 6.7 HEATING AND AIR CONDITIONING (SEP 2000)

# A. BUILDING SHELL:

- Temperatures shall conform to local commercial equivalent temperature levels and operating practices in order to maximize tenant satisfaction. These temperatures shall be maintained throughout the leased premises and service areas, regardless of outside temperatures, during the hours of operation specified in the lease.
- During non-working hours, heating temperatures shall be set no higher than 55° Fahrenheit, and air conditioning shall not
  be provided except as necessary to return space temperatures to a suitable level for the beginning of working hours.
  Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the GSA Field
  Office Manager.
- 3. Simultaneous heating and cooling are not permitted.
- Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.
- Equipment Performance. Temperature control for office spaces shall be assured by concealed central heating and air conditioning equipment. The equipment shall maintain space temperature control over a range of internal load fluctuations of plus 0.5 W/sq.ft. to minus 1.5 W/sq.ft. from initial design requirements of the tenant.
- 6. HVAC Use During Construction. The permanent HVAC system may be used to move both supply and return air during the construction process only if the following conditions are met:
  - a. a complete air filtration system with 60 percent efficiency filters is installed and properly maintained;
  - b. no permanent diffusers are used;
  - c. no plenum-type return air system is employed;
  - d. the HVAC duct system is adequately sealed to prevent the spread of airborne particulate and other contaminants; and
  - e. following the building "flush-out," all duct systems are vacuumed with portable high-efficiency particulate arrestance (HEPA) vacuums and documented clean in accordance with National Air Duct Cleaners Association (NADCA) specifications.
- Ductwork Re-use and Cleaning. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.
- 8. Insulation. All insulation shall contain recovered materials as required by EPA's CPG and related recycled content recommendations.
- The Lessor shall conduct HVAC system balancing after any HVAC system alterations during the term of the lease and shall make a reasonable attempt to schedule major construction outside of office hours.

# B. TENANT IMPROVEMENT INFORMATION:

1. Zone Control. Individual thermostat control shall be provided for office space with control areas not to exceed 2,000 ANSI/BOMA Office Area square feet. Areas which routinely have extended hours of operation shall be environmentally controlled through dedicated heating and air conditioning equipment. Special purpose areas (such as photocopy centers, large conference rooms, computer rooms, etc.) with an internal cooling load in excess of 5 tons shall be independently controlled. Concealed package air conditioning equipment shall be provided to meet localized spot cooling of tenant special equipment. Portable space heaters are prohibited from use.

# 6.8 VENTILATION (NCR VARIATION (AUG 2002))

- A. During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the latest edition of ANSI/ASHRAE Standard 62, Ventilation for Acceptable Indoor Air Quality. Where ASHRAE Standard 62 and local codes conflict, the more stringent shall apply.
- B. Air filtration shall be provided and maintained with filters having a minimum efficiency rating as determined by ANSI/ASHRAE Standard 52.2, Method of Testing General Ventilation Air Cleaning Devices for Removal Efficiency by Particle Size. Pre-filters shall be 30 percent to 35 percent efficient. Final filters shall be 80 percent to 85 percent efficient for particles at 3 microns.
- C. Where the Lessor proposes that the Government shall pay utilities, the following shall apply:
  - 1. an automatic air or water economizer cycle shall be provided to all air handling equipment, and
  - the building shall have a fully functional building automation system capable of control, regulation, and monitoring of all environmental conditioning equipment. The building automation system shall be fully supported by a service and maintenance contract.

INITIALS: LESSOR & GOV"

#### 6.9 **VENTILATION: TOILET ROOMS (DEC 1993)**

Toilet rooms shall be properly exhausted, with a minimum of 10 air changes per hour.

#### 6.10 **ELECTRICAL: GENERAL (SEP 2000)**

The Lessor shall be responsible for meeting the applicable requirements of local codes and ordinances. When codes conflict, the more stringent standard shall apply. Main service facilities shall be enclosed. The enclosure may not be used for storage or other purposes and shall have door(s) fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch. Distribution panels shall be circuit breaker type with 10 percent spare power load and circuits.

### **ELECTRICAL: DISTRIBUTION (SEP 2000)** 6.11

# A. BUILDING SHELL:

- Main power distribution switchboards and distribution and lighting panel boards shall be circuit breaker type with copper buses that are properly rated to provide the calculated fault circuits. All power distribution panel boards shall be supplied with separate equipment ground buses. All power distribution equipment shall be required to handle the actual specified and projected loads plus 10 percent spare load capacity. Distribution panels are required to accommodate circuit breakers for the actual calculated needs plus 10 percent spare circuits that will be equivalent to the majority of other circuit breakers in the panel system. All floors shall have 120/208 V, 3-phase, 4-wire with bond, 60 hertz electric service available.
- Main distribution for standard office occupancy shall be provided at the Lessor's expense. In no event shall such power distribution (not including lighting and HVAC) for the Government-demised area fall below 7 W per ANSI/BOMA Office Area square foot.
- 3. Convenience outlets shall be installed in accordance with NFPA Standard 70, National Electrical Code, or local code, whichever is more stringent.

### B. TENANT IMPROVEMENT INFORMATION:

- All electrical, telephone, and date outlets within the Government-demised area shall be installed by the Lessor at the expense of the Government in accordance with the design intent drawings. All electrical outlets shall be installed in accordance with NFPA Standard 70, or local code, whichever is more stringent.
- All tenant outlets shall be marked and coded for ease of wire tracing; outlets shall be circuited separately from lighting. All floor outlets shall be flush with the plane of the finished floor.
- 3. The Lessor shall ensure that outlets and associated wiring (for electricity, voice, and data) to the workstation(s) shall be safely concealed in partitions, ceiling plenums, in recessed floor ducts, under raised flooring, or by use of a method acceptable to the Contracting Officer. In any case, cable on the floor surface shall be minimized.

# **ELECTRICAL: ADDITIONAL DISTRIBUTION SPECIFICATIONS**

If the Offeror proposes that building maintenance will be the responsibility of the Government, the Lessor shall provide duplex utility outlets in toilets, corridors, and dispensing areas for maintenance purposes at no cost to the Government. Fuses and circuit breakers shall be plainly marked or labeled to identify circuits or equipment supplied through them.

### **TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)** 6.13

# A. BUILDING SHELL:

- Sufficient space shall be provided on the floor(s) where the Government occupies space for the purposes of terminating telecommunications service into the building. The building's telecommunications closets located on all floors shall be vertically-stacked. Telecommunications switchrooms, wire closets, and related spaces shall be enclosed. The enclosure shall not be used for storage or other purposes and shall have door(s) fitted with an automatic door-closer and deadlocking latch bolt with a minimum throw of 1/2 inch.
- Telecommunications switchrooms, wire closets, and related spaces shall meet applicable Telecommunications Industry Association (TIA) and Electronic Industries Alliance (EIA) standards. These standards include the following:
  - a. TIA/EIA-568, Commercial Building Telecommunications Cabling Standard,
  - b. TIA/EIA 569, Commercial Building Standard for Telecommunications Pathways and Spaces,
  - C. TIA/EIA-570, Residential and Light Commercial Telecommunications Wiring Standard, and
  - d. TIA/EIA-607, Commercial Building Grounding and Bonding Requirements for Telecommunications Standard.
- 3. Telecommunications switchrooms, wire closets, and related spaces shall meet applicable NFPA standards. Bonding and grounding shall be in accordance with NFPA Standard 70, National Electrical Code, and other applicable NFPA standards and/or local code requirements.

## **B. TENANT IMPROVEMENT INFORMATION:**

Telecommunications floor or wall outlets shall be provided as required. At a minimum, each outlet shall house one 4-pair wire jack for voice and one 4-pair wire jack for data. The Lessor shall ensure that all outlets and associated wiring, copper, coaxial cable,

INITIALS: LESSOR & DOLLAR

optical fiber, or other transmission medium used to transmit telecommunications (voice, data, video, Internet, or other emerging technologies) service to the workstation shall be safely concealed under raised floors, in floor ducts, walls, columns, or molding. All outlets/junction boxes shall be provided with rings and pull strings to facilitate the installation of cable. Some transmission medium may require special conduit, inner duct, or shielding as specified by the Government.

# 6.14 TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (SEP 2000)

### A. BUILDING SHELL:

- 1. The Government reserves the right to contract its own telecommunications (voice, data, video, Internet or other emerging technologies) service in the space to be leased. The Government may contract with one or more parties to have inside wiring (or other transmission medium) and telecommunications equipment installed.
- 2. The Lessor shall allow the Government's designated telecommunications providers access to utilize existing building wiring to connect its services to the Government's space. If the existing building wiring is insufficient to handle the transmission requirements of the Government's designated telecommunications providers, the Lessor shall provide access from the point of entry into the building to the Government's floor space, subject to any inherent limitations in the pathway involved.
- 3. The Lessor shall allow the Government's designated telecommunications providers to affix telecommunications antennae (high frequency, mobile, microwave, satellite, or other emerging technologies), subject to weight and wind load conditions, to roof, parapet, or building envelope as required. Access from the antenna(e) to the leased space shall be provided.
- 4. The Lessor shall allow the Government's designated telecommunications providers to affix antennae and transmission devices throughout its leased space and in appropriate common areas frequented by the Government's employees so as to allow the use of wireless telephones and communications devices necessary to conduct business.

# B. TENANT IMPROVEMENT INFORMATION:

Should the Government's security requirements require sealed conduit to house the telecommunications transmission medium, the Lessor shall provide such conduit at the expense of the Government.

### 6.15 DATA DISTRIBUTION (SEP 2000)

# A. TENANT IMPROVEMENT INFORMATION:

The Government shall at its expense be responsible for purchasing and installing data cable. The Lessor shall ensure that data outlets and the associated wiring used to transmit data to workstations shall be safely concealed in floor ducts, walls, columns, or below access flooring. The Lessor shall provide outlets, which shall include rings and pull strings to facilitate the installation of the data cable. When cable consists of multiple runs, the Lessor shall provide ladder-type cable trays to insure that Government-provided cable does not come into contact with suspended ceilings. Cable trays shall form a loop around the perimeter of the Government-demised area such that they are within a 30-foot, 0-inch horizontal distance of any single drop.

# 6.16 ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (SEP 2000)

# A. TENANT IMPROVEMENT INFORMATION:

- 1. The Lessor shall provide as part of the Tenant Improvement Allowance separate data, telephone, and electric junction boxes for the base feed connections to Government-provided modular or systems furniture, when such feeds are supplied via wall outlets or floor penetrations. When overhead feeds are used, junction boxes shall be installed for electrical connections. Raceways shall be provided throughout the furniture panels to distribute the electrical, telephone, and data cable. The Lessor shall provide all electrical service wiring and connections to the furniture at designated junction points. Each electrical junction shall contain an 8-wire feed consisting of 3 general-purpose 120-V circuits with 1 neutral and 1 ground wire, and a 120-V isolated-ground circuit with 1 neutral and 1 isolated-ground wire. A 20-ampere circuit shall have no more than 8 general-purpose receptacles or 4 isolated-ground "computer" receptacles.
- 2. The Government shall at its expense be responsible for purchasing data and telecommunications cable. Said cable shall be installed and connected to systems furniture by the Lessor/contractor with the assistance and/or advice of the Government or computer vendor. The Lessor shall provide wall-mounted data and telephone junction boxes, which shall include rings and pull strings to facilitate the installation of the data and telecommunications cable. When cable consists of multiple runs, the Lessor shall provide ladder-type cable trays to insure that Government-provided cable does not come into contact with suspended ceilings. Cable trays shall form a loop around the perimeter of the Government-demised area such that they are within a 30-foot, 0-inch horizontal distance of any single drop. Said cable trays shall provide access to both telecommunications data closets and telephone closets.
- 3. The Lessor shall furnish and install suitably sized junction boxes in the vicinity of the "feeding points" of the furniture panels. All "feeding points" shall be shown on Government-approved design intent drawings. The Lessor shall temporarily cap off the wiring in the junction boxes until the furniture is installed during Phase 2. The Lessor shall make all connections in the power panel and shall keep the circuit breakers off. The Lessor shall identify each circuit with the breaker number and shall identify the computer hardware to be connected to it. The Lessor shall identify each breaker at the panel and identify the devices that it serves.
- 4. PHASE 2 involves the Lessor's electrical contractor connecting power poles or base feeds in the junction boxes to the furniture electrical system and testing all pre-wired receptacles in the systems furniture. It also involves other Government contractors who will be installing the data cable in the furniture panels for the terminal and printer locations, installing the connectors on the terminal/printer ends of the cable, and continuity testing each cable. All Phase 2 work shall be coordinated and performed in conjunction with the furniture, telephone, and data cable installers. Much of this work may occur over a weekend on a schedule that requires flexibility and on-call visits.

INITIALS: 4 & C

& GOV'T

## 6.17 ADDITIONAL ELECTRICAL CONTROLS

If the Offeror proposes that the Government pay separately for electricity, no more than 500 square feet of office may be controlled by one switch or automatic light control for all space on the Government meter, either through a building automation system, time clock, occupant sensor, or other comparable system acceptable to the Contracting Officer.

### 6.18 ELEVATORS (NCR VARIATION (AUG 2002))

A. The lessor shall provide suitable passenger and freight elevator service to any Government-demised area not having ground level access. Service shall be available during the hours specified in the "Normal Hours" paragraph in the SERVICES, UTILITIES, and MAINTENANCE section of this SFO. However, one passenger and one freight elevator shall be available at all times for Government use. The freight elevator shall be accessible to the loading areas. When possible, the Government shall be given 24-hour advance notice if the service is to be interrupted for more than 1-1/2 hours. Normal service interruption shall be scheduled outside of the Government's normal working hours. The Lessor shall also use best efforts to minimize the frequency and duration of unscheduled interruptions.

### B CODE:

In buildings being constructed or undergoing major modernization, the elevators shall conform to the current edition of the American Society of Mechanical Engineers ASME A17.1 Safety Code for Elevators and Escalators. Existing buildings shall conform to the current edition of ASME A17.3 Safety Code for Existing Elevators and Escalators. Elevator lobby smoke detectors shall activate the building fire alarm system, signal the fire department or central station and capture the elevators. The elevators shall be inspected and maintained in accordance with the current edition of ASME A17.2.1 or A17.2.2, Inspectors Manual for Electronic and Hydraulic Elevators. All elevators shall meet both the ADAAG and the UFAS requirements.

### C. <u>SAFETY SYSTEMS</u>:

Elevators shall be equipped with a means of two way voice communication (telephone, intercom, etc.) between the car and a readily accessible point outside the hoistway, which is available to emergency personnel 24 hours a day. An audible signaling device shall be provided. Both the two way voice communication and audible signaling device need to be backed-up with a battery or emergency power source. The back up system shall be clearly identified.

### D. SPEED

The passenger elevators shall have the capacity to transport in 5 minutes 15 percent of the normal population of all upper floors (based on 200 rentable square feet of leased space for each person). Further the dispatch interval between elevators during the up-peak demand period shall not exceed 35 seconds.

## E. <u>INTERIOR FINISHES</u>:

Elevator cab walls shall be hardwood, marble, granite, or an equivalent pre-approved by the Contracting Officer. Elevator cab floors shall be marble, granite, terrazzo, or an equivalent pre-approved by the Contracting Officer.

## 6.19 LIGHTING: INTERIOR AND PARKING (NOV 2005)

## A. BUILDING SHELL:

- 1. The Lessor shall provide interior lighting, as part of the building shell cost, in accordance with the following:
  - a. Modern, diffused fluorescent fixtures using no more than 2.0 W per ANSI/BOMA Office Area square foot shall be provided. Such fixtures shall be capable of producing a light level of 50 average maintained foot-candles at working surface height throughout the space. Tubes shall then be removed to provide 1) 30 foot-candles in portions of work areas other than work surfaces and 2) 1 foot-candle to 10 foot-candles, or minimum levels sufficient to ensure safety, in non-working areas. Exceptions may be granted by the GSA Buildings Manager. When the space is not in use by the Government, interior and exterior lighting, except that essential for safety and security purposes, shall be turned off.
  - b. Exterior parking areas, vehicle driveways, pedestrian walkways, and building perimeter shall have 5 foot-candles for doorway areas, 3 foot-candles for transition areas (including stairwells), and at least 1 foot-candle overlapping throughout the lot, except where local codes conflict. Illumination shall be designed based on Illuminating Engineering Society of North America (IESNA) standards. Indoor parking shall have a minimum of 10 foot-candles and shall be designed based on IESNA standards. The intent is to provide adequate lighting at entrances/exits, garages, parking lots or other adjacent areas to the building to discourage crimes against persons.
  - c. Exterior building lighting must have emergency power backup to provide for safe evacuation of the building in case of natural disaster, power outage, or criminal/terrorist activity.
  - d. The Lessor shall provide occupancy sensors and/or scheduling controls through the building automation system to reduce the hours that the lights are on when the space is unoccupied. Daylight dimming controls shall be used in atriums or other space where daylight can contribute to energy savings.
  - e. Lighting shall be controlled by occupancy sensors arranged to control open areas, individual offices, conference rooms, toilet rooms within the Government-demised area, and all other programmed spaces or rooms within the leased space. The control system shall provide an optimal mix of infrared and ultrasonic sensors suitable for the configuration and type of space. Occupancy sensors shall be located so that they have a clear view of the room or area they are monitoring. No more than 1,000 ANSI/BOMA Office Area square feet of open space shall be controlled by occupancy sensor. All occupancy sensors shall have manual switches to override the light control. Such switches shall be

INITIALS: 4 & COVIT

SFO NO.06-031 09/07/06 located by door openings in accordance with both the ADAAG and the UFAS. If light switches are to be used instead of occupancy sensors or in combination with occupancy sensors, the Offeror shall notify the Government during the negotiation process.

# 6.20 LIGHTING: INTERIOR AND PARKING (NOV 2005)

## A. BUILDING SHELL:

- 1. The Lessor shall provide interior lighting, as part of the building shell cost, in accordance with the following:
  - a. The Lessor shall provide deep-cell parabolic louver 2'-0" wide x 4'-0" high or 2'-0" wide x 2'-0" high (or building standard that meets or exceeds this standard) fluorescent lighting fixtures with energy-efficient lamps (T8 or better) and electronic ballasts for standard interior lighting. Such fixtures shall produce 50 average maintained foot-candles at working surface height throughout work spaces, 20 foot-candles in corridors, and 10 foot-candles in other non-working areas.
  - b. Exterior parking areas, vehicle driveways, pedestrian walkways, and building perimeter shall have 5 foot-candles for doorway areas, 3 foot-candles for transition areas (including stairwells), and at least 1 foot-candle overlapping throughout the lot, except where local codes conflict. A minimum of 1 foot-candle of Illumination and shall be designed based on Illuminating Engineering Society of North America (IESNA) standards. Indoor parking shall have a minimum of 10 foot-candles and shall be designed based on IESNA standards. The intent is to provide adequate lighting at entrances/exits, garages, parking lots or other adjacent areas to the building to discourage crimes against persons.
  - Exterior building lighting must have emergency power backup to provide for safe evacuation of the building in case of natural disaster, power outage, or criminal/terrorist activity.
  - d. The Lessor shall provide occupancy sensors and/or scheduling controls through the building automation system to reduce the hours that the lights are on when the space is unoccupied. Daylight dimming controls shall be used in atriums or other space where daylight can contribute to energy savings.
  - e. Lighting shall be controlled by occupancy sensors arranged to control open areas, individual offices, conference rooms, toilet rooms within the Government-demised area, and all other programmed spaces or rooms within the leased space. The control system shall provide an optimal mix of infrared and ultrasonic sensors suitable for the configuration and type of space. Occupancy sensors shall be located so that they have a clear view of the room or area they are monitoring. No more than 1,000 ANSI/BOMA Office Area square feet of open space shall be controlled by occupancy sensor. All occupancy sensors shall have manual switches to override the light control. Such switches shall be located by door openings in accordance with both the ADAAG and the UFAS. If light switches are to be used instead of occupancy sensors or in combination with occupancy sensors, the Offeror shall notify the Government during the negotiation process.

### 7.0 SERVICES, UTILITIES, MAINTENANCE

## 7.1 SERVICES, UTILITIES, MAINTENANCE: GENERAL (NCR VARIATION (AUG 2002))

- A. Services, utilities, and maintenance shall be provided by the Lessor as part of the rental consideration. The Lessor shall have a building superintendent or a locally designated representative available to promptly correct deficiencies.
- B. At the Government's expense, the Lessor shall be responsible for preventive maintenance and repair of all special, Government specified, new or existing Government owned mechanical, electrical, and plumbing equipment (excluding computers, telephone systems, and other communication equipment) installed by the Lessor and as identified by the Government. The cost of the maintenance will be negotiated as an increase in base rent by adjusting the base operating expense and service and utility rate per square foot, either before or after award of the lease, once the scope of work has been identified. An adjustment to the option term base operating expenses and service and utility rate per square foot shall also be negotiated.

# 7.2 NORMAL HOURS

Services, utilities, and maintenance shall be provided daily, extending 7:00 a.m. to 7:00 p.m. and 8:00 a.m. to 4:00 p.m. on Saturdays excluding Sundays and federal holidays.

### 7.3 OVERTIME USAGE (SEP 2000)

- A. The Government shall have access to the leased space at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, toilets, lights, and electric power.
- B. If heating or cooling is required on an overtime basis, such services will be ordered orally or in writing by the Contracting Officer or the GSA Buildings Manager. When ordered, services shall be provided at the hourly rate established in the contract. Costs for personal services shall only be included as authorized by the Government.
- C. When the cost of service is \$2,000 or less, the service may be ordered orally. An invoice shall be submitted to the official placing the order for certification and payment. Orders for services costing more than \$2,000 shall be placed using GSA Form 300, Order for Supplies or Services. The two clauses from GSA Form 3517, General Clauses, 552.232-75, Prompt Payment, and 552.232-70, Invoice Requirements (Variation), apply to all orders for overtime services.

INITIALS:

& GOV'T

All orders are subject to the terms and conditions of this lease. In the event of a conflict between an order and this lease, the lease shall control

### 7.4

The Lessor shall ensure that utilities necessary for operation are provided and that all associated costs are included as a part of the established rental rate.

#### 7.5 **BUILDING OPERATING PLAN**

If the cost of utilities is not included as part of the rental consideration, the Offeror shall submit a building operating plan with the offer. Such plan shall include a schedule of startup and shutdown times for operation of each building system, such as lighting, HVAC, and plumbing which is necessary for the operation of the building. Such plan shall be in operation on the effective date of the lease.

#### **JANITORIAL SERVICES (SEP 2000)** 7.6

A. Daytime cleaning is required for the entire space, except for the storage space. Cleaning shall be performed after tenant working hours unless daytime cleaning is specified as a special requirement elsewhere in this SFO.

## SELECTION OF CLEANING PRODUCTS:

Wherever reasonably practicable (based on considerations of cost, efficacy, and availability), the Lessor shall use commercially reasonable efforts to utilize cleaning equipment, methods, supplies and products that incorporate environmentally beneficial practices, recycled content, biodegradable and phosphate-free ingredients, which are intended to minimize the use of corrosive, flammable, harsh or irritating chemicals or environmentally wasteful practices and packaging.

- C. The Lessor shall maintain the leased premises, including outside areas, in a clean condition and shall provide supplies and equipment. The following schedule describes the level of services intended. Performance will be based on the Contracting Officer's evaluation of results, not the frequency or method of performance.
  - 1. Daily. Empty trash receptacles, and clean ashtrays. Sweep entrances, lobbies, and corridors. Spot sweep floors, and spot vacuum carpets. Clean drinking fountains. Sweep and damp mop or scrub toilet rooms. Clean all toilet fixtures, and replenish toilet supplies. Dispose of all trash and garbage generated in or about the building. Wash inside and out or steam clean cans used for collection of food remnants from snack bars and vending machines. Dust horizontal surfaces that are readily available and visibly require dusting. Spray buff resilient floors in main corridors, entrances, and lobbies. Clean elevators and escalators. Remove carpet stains. Police sidewalks, parking areas, and driveways. Sweep loading dock areas and platforms.
  - 2. Three Times a Week. Sweep or vacuum stairs.
  - Weekly. Damp mop and spray buff all resilient floors in toilets and health units. Sweep sidewalks, parking areas, and driveways (weather permitting).
  - 4. Every Two Weeks. Spray buff resilient floors in secondary corridors, entrance, and lobbies. Damp mop and spray buff hard and resilient floors in office space.
  - Monthly. Thoroughly dust furniture. Completely sweep and/or vacuum carpets. Spot clean all wall surfaces within 70 inches of the floor.
  - 6. Every Two Months. Damp wipe toilet wastepaper receptacles, stall partitions, doors, window sills, and frames. Shampoo entrance and elevator carpets.
  - 7. Three Times a Year. Dust wall surfaces within 70 inches of the floor, vertical surfaces and under surfaces. Clean metal and marble surfaces in lobbies. Wet mop or scrub elevator lobbies in garage.
  - 8. Twice a Year. Wash all exterior windows and other glass surfaces. Strip and apply four coats of finish to resilient floors in toilets, if applicable. Strip and refinish main corridors and other heavy traffic areas, if applicable.
  - 9. Annually. Vacuum or dust all surfaces in the building of 70 inches from the floor. Strip and refinish floors in offices and secondary lobbies and corridors. Shampoo carpets in corridors and lobbies. Clean balconies, ledges, courts, areaways, and flat roofs. Power wash garage floors.
  - 10. As Required. Properly maintain plants and lawns. Remove snow and ice from entrances, exterior walks, and parking lots of the building. Provide initial supply, installation, and replacement of light bulbs, tubes, ballasts, and starters. Replace worn floor coverings (this includes the moving and returning of furnishings) in the common areas. Control pests as appropriate, using Integrated Pest Management techniques.

INITIALS: 4 & DOUT

## 7.7 SCHEDULE OF PERIODIC SERVICES (NCR VARIATION (AUG 2002))

Within 60 days after occupancy by the Government, the Lessor shall provide the Contracting Officer with a detailed written schedule of all periodic services and maintenance to be performed other than daily, weekly, or monthly. Such schedule shall be updated in writing to the Contracting Officer every two (2) years.

### 7.8 LANDSCAPE MAINTENANCE

Performance will be based on the Contracting Officer's evaluation of results and not the frequency or the method of performance. Landscape maintenance shall be performed during the growing season on a weekly cycle and shall consist of watering, mowing, and policing the area to keep it free of debris. Pruning and fertilization shall be done on an as needed basis. In addition, dead or dying plants shall be replaced.

### 7.9 FLAG DISPLAY

The Lessor shall be responsible for flag display on all workdays and federal holidays. The Government will provide instructions when flags shall be flown at half-staff.

## 7.10 MAINTENANCE AND TESTING OF SYSTEMS (SEP 2000)

- A. The Lessor is responsible for the total maintenance and repair of the leased premises. Such maintenance and repairs include site and private access roads. All equipment and systems shall be maintained to provide reliable, energy-efficient service without unusual interruption, disturbing noises, exposure to fire or safety hazards, uncomfortable drafts, excessive air velocities, or unusual emissions of dirt. The Lessor's maintenance responsibility includes initial supply and replacement of all supplies, materials, and equipment necessary for such maintenance. Maintenance, testing, and inspection of appropriate equipment and systems shall be done in accordance with applicable codes, and inspection certificates shall be displayed as appropriate. Copies of all records in this regard shall be forwarded to the GSA Field Office Manager or a designated representative.
- B. Without any additional charge, the Lessor will provide at Government request, documentation of proper operations or testing prior to occupancy of such systems as fire alarm, sprinkler, emergency generator, etc. to ensure proper operation. These tests shall be witnessed by a designated representative of the Contracting Officer.

### 8.0 SAFETY AND ENVIRONMENTAL MANAGEMENT

# 8.1 OCCUPANCY PERMIT (SEP 2000)

The Lessor shall provide a valid occupancy permit for the intended use of the Government and shall maintain and operate the building in conformance with current local codes and ordinances. If the local jurisdiction does not issue occupancy permits, the Offeror shall consult the Contracting Officer to determine if other documentation may be needed.

## 8.2 FIRE AND LIFE SAFETY (SEP 2003)

- A. Offered space must meet or be upgraded to meet the applicable egress requirements in NFPA Standard No. 101, *Life Safety Code*, or equivalent prior to occupancy. The space must provide access to a minimum of two remote exits on each floor of Government occupancy. Scissor stairs shall only be counted as one exit stairway and 'open air' exterior fire escapes shall not be counted as an approved exit.
- B. If offered space is 3 or more floors above the lowest level of fire department vehicle access, the Offeror must provide written confirmation that the building has a building wide fire alarm system in compliance with either the requirements of NFPA Standard No. 72 (current as of the date of this SFO) or the requirements of the local building and fire codes and ordinances (current as of the date of this SFO) adopted by the jurisdiction in which the building is located.
- C. If offered space is 6 or more floors above the lowest level of fire department access, additional fire and life safety requirements will apply

## 8.3 AUTOMATIC SPRINKLER SYSTEM ((NCR VARIATION) JUL 2004)

- A. Below-grade space to be occupied by Government and all areas in a building referred to as "hazardous areas" in National Fire Protection Association (NFPA) Standard No.101, Life Safety Code, shall be protected by an automatic sprinkler system or an equivalent level of safety.
- B. Buildings in which any portion of the offered space is on or above the sixth floor, and lease of the offered space will result, either individually or in combination with other Government leases in the offered building, in the Government leasing 35,000 ANSI/BOMA Office Area square feet or more of space in the offered building, then the entire building shall be protected by an automatic sprinkler system or an equivalent level of safety. Buildings in which any portion of the offered space is on or above the sixth floor, and lease of the offered space will result, either individually or in combination with other Government leases in the offered building, in the Government leasing less than 35,000 ANSI/BOMA Office Area square feet of space in the offered building, shall be protected by an automatic sprinkler system or an equivalent level of safety from the highest floor of government occupancy down to the lowest level in the building.

INITIALS:

: LESSOR

C. If an offeror proposes to satisfy any requirement of the above sub-paragraphs by providing an equivalent level of safety, the offeror shall submit, for Government review and approval, a fire protection engineering analysis, performed by a qualified fire protection engineer, demonstrating that an equivalent level of safety for the offered building exists. The offeror shall contact the Contracting Officer for further information regarding Government review and approval of the "equivalent level of safety" analyses. Refer to 41 CFR Part 102-80 for guidance on conducting an equivalent level of safety analysis.

### D. Definitions:

- (1) "Equivalent level of safety" means an alternative design or system (which may include automatic sprinkler systems), based upon fire protection engineering analysis, which achieves a level of safety equal to or greater than that provided by automatic sprinkler systems.
  - "Automatic sprinkler system" for fire protection purposes means an electronically supervised, integrated system of underground and overhead piping, designed in accordance with NFPA Standard No. 13. The system is usually activated by heat from fire and discharges water over the fire area. The system includes a suitable water supply.

# 8.4 FIRE ALARM SYSTEMS ((NCR VARIATION) JUL 2004)

- A. Fire alarm systems shall be provided in accordance with the requirements of NFPA Standard No. 72. If the fire alarm system is over 25 years old, a new voice fire alarm system must be installed prior to Government acceptance and occupancy of the offered space per the latest building code and NFPA 72. If the fire alarm system is over 10 years old, a copy of all maintenance records for the past two years shall be submitted as part of SFO Attachment # 4 to the offeror's proposal. The information shall be reviewed by the Government to determine whether a new fire alarm system will be required. If a new fire alarm system is required, the offeror will be required to provide such system at its sole cost and expense prior to Government acceptance and occupancy of the offered space.
- B. The fire alarm system shall be maintained by the lessor in accordance with NFPA Standard No. 72. The fire alarm system wiring and equipment must be electrically supervised and automatically notify the local fire department (NFPA Standard No. 72) or approved central station. Emergency power must be provided in accordance with NFPA Standards 70 and 72.

## 8.5 OSHA REQUIREMENTS (SEP 2000)

The Lessor shall maintain buildings and space in a safe and healthful condition according to OSHA standards.

## 8.6 ASBESTOS (SEP 2000)

- A. Offers are requested for space with no asbestos-containing materials (ACM), or with ACM in a stable, solid matrix (e.g., asbestos flooring or asbestos cement panels) which is not damaged or subject to damage by routine operations. For purposes of this paragraph, "space" includes the 1) space offered for lease; 2) common building areas; 3) ventilation systems and zones serving the space offered; and 4) the area above suspended ceilings and engineering space in the same ventilation zone as the space offered. If no offers are received for such space, the Government may consider space with thermal system insulation ACM (e.g., wrapped pipe or boiler lagging) which is not damaged or subject to damage by routine operations.
- B. Definition. ACM is defined as any materials with a concentration of greater than 1 percent by dry weight of asbestos.
- C. Space with ACM of any type or condition may be upgraded by the Offeror to meet the conditions described in subparagraph A by abatement (removal, enclosure, encapsulation, or repair) of ACM not meeting those conditions. If an offer involving abatement of ACM is accepted by the Government, the Lessor shall, prior to occupancy, successfully complete the abatement in accordance with OSHA, EPA, Department of Transportation (DOT), state, and local regulations and guidance.
- D. Management Plan. If space is offered which contains ACM, the Offeror shall submit an asbestos-related management plan for acceptance by the Government prior to lease award. This plan shall conform to EPA guidance, be implemented prior to occupancy, and be revised promptly when conditions affecting the plan change. If asbestos abatement work is to be performed in the space after occupancy, the Lessor shall submit to the Contracting Officer the occupant safety plan and a description of the methods of abatement and reoccupancy clearance, in accordance with OSHA, EPA, DOT, state, and local regulations and guidance, at least 4 weeks prior to the abatement work.

## 8.7 INDOOR AIR QUALITY (SEP 2000)

- A. The Lessor shall control contaminants at the source and/or operate the space in such a manner that the GSA indicator levels for carbon monoxide (CO), carbon dioxide (CO<sub>2</sub>), and formaldehyde (HCHO) are not exceeded. The indicator levels for office areas shall be: CO 9 ppm time-weighted average (TWA 8-hour sample); CO<sub>2</sub> 1,000 ppm (TWA); HCHO 0.1 ppm (TWA).
- B. The Lessor shall make a reasonable attempt to apply insecticides, paints, glues, adhesives, and HVAC system cleaning compounds with highly volatile or irritating organic compounds, outside of working hours. The Lessor shall provide at least 72 hours advance notice to the Government before applying noxious chemicals in occupied spaces and shall adequately ventilate those spaces during and after application.
- C. The Lessor shall promptly investigate indoor air quality (IAQ) complaints and shall implement the necessary controls to address the complaint.
- D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in space that it occupies, as well as in space serving the Government-demised area (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by 1) making available information on building operations and Lessor activities; 2) providing access to space for assessment and testing, if required; and 3) implementing corrective measures required by the Contracting Officer.

INITIALS: LESSOR & COVIT

E. The Lessor shall provide to the Government material safety data sheets (MSDS) upon request for the following products prior to their use during the term of the lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the right to review such products used by the Lessor within 1) the Government-demised area; 2) common building areas; 3) ventilation systems and zones serving the leased space; and 4) the area above suspended ceilings and engineering space in the same ventilation zone as the leased space.

#### 8.8 RADON IN AIR (SEP 2000)

If space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy. test the leased space for 2 days to 3 days using charcoal canisters or electret ion chambers to ensure that radon in air levels are below EPA's action concentration of 4 picoCuries per liter. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors or electret ion chambers shall be completed.

#### **RADON IN WATER (SEP 2000)** 8.9

- A. The Lessor shall demonstrate that water provided in the leased space is in compliance with EPA requirements and shall submit certification to the Contracting Officer prior to the Government occupying the space.
- If the EPA action level is reached or exceeded, the Lessor shall institute appropriate abatement methods which reduce the radon levels to below this action level.

#### 8.10 **HAZARDOUS MATERIALS (OCT 1996)**

The leased space shall be free of hazardous materials according to applicable federal, state, and local environmental regulations.

#### 8.11 **RECYCLING (SEP 2000)**

Where state and/or local law, code, or ordinance require recycling programs for the space to be provided pursuant to this SFO, the successful Offeror shall comply with such state and/or local law, code, or ordinance in accordance with GSA Form 3517, General Clauses, 552.270-8, Compliance with Applicable Law. In all other cases, the successful Offeror shall establish a recycling program in the leased space where local markets for recovered materials exist. The Lessor agrees, upon request, to provide the Government with additional information concerning recycling programs maintained in the building and in the leased space.

#### 8.12 **OCCUPANT EMERGENCY PLANS (NOV 2005)**

The Lessor is required to participate in the development and implementation of the Government Occupant Emergency Plan. The Occupant Emergency Plan shall include procedures for notification of the Lessor's building engineer or manager, building security, local emergency personnel, and GSA personnel for possible shutdown of the air-handling units.

#### 9.0 LEASE SECURITY STANDARDS

#### **GENERAL REQUIREMENTS (NOV 2005)** 9.1

- Overview of Lease Security Standards:
  - The Government will determine security standards for facilities and agency space requirements. Security standards will be assessed based upon tenant agency mix, size of space requirement, number of employees, use of the space, location of the facility, configuration of the site and lot, and public access into and around the facility. The Government will designate a security level from Level I to Level IV for each space requirement. The Contracting Officer (or the Contracting Officer's designated representative) will provide the security level designation as part of the space requirement. A copy of the Government's security standards is available at www.oca.gsa.gov.
  - The Contracting Officer (or the Contracting Officer's designated representative) will identify all required security standards.
  - 3. Any security-related alterations (i) are to be limited to ONDCP's Leased Premises; (ii) require the Government to submit plans and specifications for the proposed work to the Lessor for Lessor's prior review and written approval, which approval shall not be unreasonably withheld; and (iii) the Government must, at the Lessor's option, remove such alterations when it vacates the leased premises and restore the premises to the condition they were in prior to such alterations being made.
  - A security level designation may be determined by the individual space requirement or by the assessed, cumulative tenant agency mix within a given facility. If an Offeror is offering space in a facility currently housing a federal agency, the security level designation of the facility may be increased and the Offeror may be required to adhere to a higher security standards to be mutually agreed upon by Landlord and Tenant, at the Government's cost.
  - Level I requirements have been incorporated into the paragraphs entitled, Lighting: Interior and Parking, and Doors: Hardware as part of this SFO. If this SFO is used for a Level I space requirement, the Level II lease security standards, as determined by the Government, shall become the minimum lease security standards for this requirement. The existing system under this paragraphs meets requirements and the Government is willing to accept "as-is", subject to Rider #2, Paragraph 1.

INITIALS: LESSOR & CANT

#### 9.2 **DETERRENCE TO UNAUTHORIZED ENTRY (NOV 2005)**

The Lessor shall provide a level of security that reasonably prevents unauthorized entry to the space during non-duty hours and deters loitering or disruptive acts in and around the space leased. The Lessor shall ensure that security cameras and lighting are not obstructed. The Landlord will take reasonable steps to attempt to prevent loitering, disruptive acts, or unauthorized entry into or around the Building, including the front entrance, garage entrance or rear loading dock, however, in the event of a known disruption or disturbance the Landlord will notify the Metropolitan DC Police Department and attempt to secure the Building by locking entry points to protect the occupants and the property.

#### 9.3 **ACCESS TO UTILITY AREAS (NOV 2005)**

Utility areas shall be secure, and only authorized personnel shall have access.

#### 9.4 **EMERGENCY POWER TO CRITICAL SYSTEMS (TENANT IMPROVEMENT) (NOV 2005)**

Emergency power backup is required for all alarm systems, CCTV monitoring devices, fire detection systems, entry control devices, lighting, etc., and special equipment, as identified elsewhere in the SFO. The existing system under this paragraphs meets requirements and the Government is willing to accept "as-is", subject to Rider#2, Paragraph 1. Any alterations to the emergency generator required by the Government are subject to the Landlord's prior approval in the Landlord's sole discretion, which shall not be unreasonably withheld, conditioned, or delayed, and if agreed to, shall be (i) performed at the Government's cost, and, (ii) at the Lessor's option, must be removed by the Government when it vacates and the property and the altered systems restored to their prior condition at the Government's cost.

#### 9.5 **MECHANICAL AREAS AND BUILDING ROOFS (NOV 2005)**

- Keyed locks, keycards, or similar security measures shall strictly control access to mechanical areas. Additional controls for access to keys, keycards, and key codes shall be strictly maintained. The Lessor shall develop and maintain accurate HVAC diagrams and HVAC system labeling within mechanical areas. The existing systems, diagrams and labeling under this paragraph meets the Government's requirements and the Government is willing to accept "as-is".
- Roofs with HVAC systems shall also be secured. Fencing or other barriers may be required to restrict access from adjacent roofs based on a Government Building Security Assessment. Roof access shall be strictly controlled through keyed locks, keycards, or similar measures.

#### **ACCESS TO BUILDING INFORMATION (NOV 2005)** 9.6

Building Information-including mechanical, electrical, vertical transport, fire and life safety, security system plans and schematics, computer automation systems, and emergency operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only **in the Lessor's reasonable discretion**, approved by the Government, preferably by the development of an access list and controlled copy numbering. The Contracting Officer may direct that the names and locations of Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the building directory. The Landlord agrees not to release plans or information relating to the Government's premises or systems to third parties except with the Government's permission, with the exception of the sixth (6th) floor partition plan to be given to prospective tenants and brokers for marketing purposes during the final nine (9) months of the Lease Term if the Government has not exercised its option to renew the lease. The Landlord will exercise reasonable diligence and discretion in providing such information to provide as safe and secure an environment as is reasonably practicable for the Government and the other tenants of the Building.

#### POSTING OF GOVERNMENT RULES AND REGULATIONS (TENANT IMPROVEMENT) (NOV 2005) 9.7

The Government will post applicable Government rules and regulations at the entrance to any Government-occupied space for such things as, but not limited to, barring the unauthorized possession of firearms and dangerous weapons. The Government will coordinate with the Lessor to ensure signage is consistent with the Lessor's standards.

#### 9.8 DEVELOPMENT, IMPLEMENTATION, AND PERIODIC REVIEW OF OCCUPANT EMERGENCY PLANS (NOV 2005)

The Lessor shall cooperate and participate in the development of an Occupant Emergency Plan (OEP) and if necessary, a supplemental Sheltering-in Place (SIP) Plan. Periodically, the Government may request that the Lessor assist in reviewing and revising the OEP and SIP plan(s).

#### 9.9 EMERGENCY VOICE/ALARM COMMUNICATION SYSTEM (BUILDING SHELL) (NOV 2005)

The building-wide fire alarm system installed in the building shall be an emergency voice/alarm communication system. The emergency voice/alarm communication system shall be designed and installed to meet the requirements of the applicable local codes and ordinances (current as of the date of this SFO) adopted by the jurisdiction in which the building is located. The emergency voice/alarm communication system shall be capable of originating and distributing voice instructions (e.g., in the event of possible contamination of the HVAC system, blasts, etc.), as well as alert and evacuation signals pertaining to fire or other emergencies to the occupants of the building. Any problems shall be reported to the Landlord and any necessary work will be done exclusively by the Lessor and/or its designated contractor(s) retained for this purpose. The Government does not have any right to make alterations to the building-wide system.

INITIALS: 4 & DOUT

#### **BUILDING SECURITY PLAN (NOV 2005)** 9.10

The Offeror shall provide a Pre-Lease Building Security Plan, as attached, with the offer that addresses its compliance with the lease security standards, as described in this SFO and its attachments.

#### 9.11 ADDITIONAL SECURITY MEASURES AS DETERMINED BY THE GOVERNMENT (NOV 2005)

The Government reserves the right with Lessor approval, such approval shall not be unreasonably withheld, conditioned or delayed, to implement at the Government's cost additional security measures within Government Occupied Space, to meet specific tenant occupancy requirements, as may be determined by the Government's building security assessment or any type of Government risk assessment evaluation of the proposed building, location, and tenant mix. The Lessor may at reasonable times enter the premises with the approval of the authorized Government representative in charge.

#### 9.12 **BACKGROUND SECURITY CHECKS (NOV 2005)**

Background Security Checks for Contract Service Personnel:

- A. The Government will conduct background checks on contractors, with routine access to Government leased space.
- B. The Lessor shall submit completed fingerprint charts and personal history statements for each employee of the Lessor as well as employees of the Lessor's contractors or subcontractors who will provide building operating services requiring routine access to the Government's leased space. The Government may also require this information for employees of the Lessor, the Lessor's contractors, or subcontractors who will be engaged to perform alterations or emergency repairs in the Government's space. For the purpose of this requirement, routine access shall be any period beyond 30 calendar days.
- C. The Contracting Officer will furnish the Lessor with Form FD-258, Fingerprint Chart, and Form 176, Statement of Personal History, to be completed by each person and returned by the Lessor to the Contracting Officer (or the Contracting Officer's designated representative) within 10 working days from receipt of the forms. Based on the information furnished, the Government will conduct security checks of the employees. The Contracting Officer will advise the Lessor in writing if an employee fails the check, and effective immediately, such employee will no longer be allowed to work or be assigned to work in the Government's space.
- D. Throughout the life of the lease, the Lessor shall provide the same data for any new employee(s), contractors, or subcontractors who will be assigned to the Government's space. In the event the Lessor's contractor/subcontractor is subsequently replaced, the new contractor/subcontractor is not required to submit another set of these forms for employees who were cleared through this process while employed by the former contractor/subcontractor. The Lessor shall resubmit Form FD-258 and Form 176 for every employee covered by this paragraph on a 3-year basis.
- E. The Lessor's Building Engineer, service personnel and any visitors to the Government-occupied area shall be required to sign in with a receptionist or guard, display a formal identification/badge, and/or require an escort.

#### 9.13 **ENTRY SECURITY: PUBLIC LOBBIES/ENTRANCES/EXITS (NOV 2005)**

- A. The Lessor may, under extreme circumstances, in response to a credible threat, permit Government security control over all public areas and building entry points, including adjacent surface parking, underground parking, and structures under the building owner's control. The Government may, under this paragraph, have the right to inspect at point of entry and in the public space. This right also includes the right to deny access and to remove persons and vehicles from the premises.
- B. The Government will have the right, with Landlord approval, such approval shall not be unreasonably withheld, conditioned or delayed, to have Security guards, provided by the Government, for the Government occupied area. The Lessor shall provide space for and facilitate the provision of such guard service, if necessary. The Government shall determine the adequacy of existing security equipment (magnetometers and x-ray) which may be installed in the Government's occupied space as part of the Government's building security assessment. The Government will provide any additional security equipment required with Landlord approval, such approval shall not be unreasonably withheld, conditioned or delayed, to have in Government occupied space. The number of guards required may be based on the Government's building security assessment and will correspond to the lobbies, entrances, exits and areas occupied, exclusively by the Government, designed for the Government's exclusive use during regular, daily business-hours. Visitor control and screening applies throughout the Government occupied space. All costs for security guards for Government accessible areas shall be born solely by the Government, and all such alterations, equipment and appurtenant hardware and connections to the Building and Building systems shall be removed by the Government when it vacates the leased premises and the premises and systems shall be restored to their condition prior to such installation or alterations, at the Government's sole cost.
- Lessor shall provide one (1) security attendant in the Main Lobby at the built-in Lobby Desk provided for this purpose during the hours of 7:00 a.m. to 11:00 p.m., Monday through Friday and 7:00 a.m. to 5:00 p.m. on Saturdays (federal holidays excepted). The attendant monitors the Building's closed circuit television (CCTV) system which has cameras installed at the main Building entrance, the entrance to the parking garage, the rear loading dock, and is connected to a digital recorder.

#### **ENTRY SECURITY: SECURITY GUARDS (NOV 2005)** 9.14

Security guards, may be provided by the Government and stationed in the immediate proximity of entrances/exits to Government occupied spaces, are required for such purposes as, ID/pass control, and staffing x-ray and magnetometer equipment. The number of security guards required may be increased or decreased, based on the Government's building security assessment, which will

INITIALS: LESSOR & D

address the quantity and location of security equipment as required below. Appropriate Government-occupied floor lobbies and entrance/exit space shall be made available for this purpose.

# 9.15 ENTRY SECURITY: X-RAY AND MAGNETOMETER AT PUBLIC ENTRANCES (NOV 2005)

Magnetometers and X-ray machines may be provided by the Government and stationed in the elevator lobbies of Government occupied floors of entrances/exits to Government occupied spaces. These devices will be provided, operated, and maintained by the Government. Armed security guards, provided by the Government, will direct the visitors through the screening equipment. Appropriate Government-occupied lobbies and entrance/exit space shall be made available for this purpose.

## 9.16 ENTRY SECURITY: INTRUSION DETECTION SYSTEM WITH CENTRAL MONITORING CAPABILITY (NOV 2005)

The Lessor shall permit installation of a perimeter Intrusion Detection System (IDS) to be operated and maintained by the Government. The existing IDS meets the Government's requirements and the Government is willing to accept the system "as-is", subject to Rider #2, Paragraph 2.

## 9.17 ENTRY SECURITY: INTERCOM (NOV 2005)

The Government accepts the existing building intercom system used in conjunction with the garage door and building entry. This system shall comply with the Architectural Barriers Act, section F230.0.

## 9.18 ENTRY SECURITY: ENTRY CONTROL WITH CCTV AND DOOR STRIKES (TENANT IMPROVEMENT) (NOV 2005)

The Government accepts the existing entry control system that will allow employees to view and communicate remotely with visitors before allowing access to Government occupied area. This system shall comply with the Architectural Barriers Act, section F230.0.

The existing **intercom and CCTV** systems under paragraphs **9.17** and **9.18** meet the Government's requirements and the Government is willing to accept **them** "as-is", subject to Rider #2, Paragraph 2. The Landlord does not have the right to remove any of the existing cameras without prior written approval of the Government.

## 9.19 OCCUPANT/VISITOR SCREENING: PHOTO IDENTIFICATION (NOV 2005)

The Government requires acceptable Government-issued photo ID for all building occupants upon entry to the Government occupied space. The Lessor may notify non-Government tenants of this requirement and assist those tenants in obtaining acceptable ID as necessary. The existing procedures under this paragraph and Section 9.13 (C )meet the Government's requirements and the Government is willing to accept it "as-is"

# 9.20 OCCUPANT/VISITOR SCREENING: VISITOR CONTROL/SCREENING SYSTEM (NOV 2005)

- A. All visitors to the building shall be required to sign in with a receptionist or guard. The Lessor shall **provide** a staffed station **in the main lobby of the building**. Public entrances and lobby space shall be made available for visitor control. The existing procedures under this paragraph meet the Government's requirements and the Government is willing to accept it "as-is".
- B. Visitor control and screening is required throughout the facility as determined by the Government's building security assessment. Underground garages and parking area entrances are also subject to visitor controls and screening. The existing procedures under this paragraph meet the Government's requirements and the Government is willing to accept it "as-is".

## 9.21 SECURE HVAC: OUTDOOR AIR INTAKES (BUILDING SHELL) (NOV 2005)

- A. The outdoor air intakes shall be located on a secure roof or high sidewall and not within 30 feet of the loading dock; otherwise the Lessor shall either relocate, extend, or secure intakes as described below as may be required by the Government:
  - 1. Outdoor air intakes shall be relocated. The lowest edge of the outdoor air intakes shall be placed 40 feet, 0 inches above grade and not less than 30 feet, 0 inches from the loading dock. Access shall be locked and secured, if feasible. For increased visibility of suspicious items, moat areas and other ground level areas surrounding outside air intakes shall be completely free of trash, debris or any other matter.
  - 2. Outdoor air intakes shall be extended. If relocation is not feasible, as approved by the Government, intake extensions shall be constructed without creating adverse effects on HVAC performance. The higher the extensions, the better, as long as other design constraints (excessive pressure loss, dynamic and static loads on structure) are considered. An extension height of 40 feet, 0 inches is required unless adverse effects on HVAC performance can be demonstrated. The entrance to the intake shall be covered with a sloped metal mesh to reduce the threat of objects being tossed in the intake. A minimum slope of 45 degrees may be required. Extension height shall be increased where existing platforms or building features (e.g., loading docks, retaining walls) might provide access to the outdoor air intakes.
  - 3. A security zone around outdoor air intakes shall be established. When outdoor air intakes are publicly accessible and relocation or physical extensions are not viable options or are cost prohibitive, perimeter barriers that prevent public access to outdoor air intake areas shall be required based on the Government's building security assessment. Iron fencing or similar see-through barriers may be required. The restricted area shall also include an open buffer zone between the public areas and the intake louvers. The Government will have the right to monitor the buffer zone by physical security and/or closed

INITIALS: LESSOR GOV'T

SFO NO.06-031 09/07/06 circuit television (CCTV). Security lighting or intrusion detection sensors are required and shall be provided and installed by the Lessor.

4. The existing air intake system meets the Government's requirements and the Government is willing to accept it "as-is".

### 9.22 SECURE HVAC: AIRBORNE HAZARDS (NOV 2005)

Air-handling units shall be able to be shut down in response to a threat. Procedures shall be in place for notification of the Lessor's building engineer or manager, building security guard desk, local emergency personnel, GSA personnel, and Contracting Officer for possible shut-down of the air handling units serving the mailroom and/or any other possibly affected areas of the building to minimize contamination, as deemed appropriate to the hazard. The existing procedures for shut down meet the Government's requirements and the Government is willing to accept them "as-is".

## 9.23 SECURE HVAC: SECURE RETURN-AIR GRILLES (BUILDING SHELL) (NOV 2005)

The Lessor shall secure return-air grilles in public lobbies. Protection measures shall not adversely affect performance of the building's HVAC system. Return air-grille protective measures can include 1) relocating return-air grilles to inaccessible, yet observable locations, 2) increasing security presence (human or CCTV) near vulnerable return-air grilles, 3) directing public access away from return-air grilles, and 4) removing furniture and visual obstructions from areas near air grilles. The existing security for the return-air grilles in public lobbies meets the Government's requirements and the Government is willing to accept them "as-is".

## 9.24 PARKING SECURITY REQUIREMENTS (NOV 2005)

### A. Control of Parking Areas:

The Lessor provides a system. The existing system for controlling the parking areas meets the Government's requirements and the Government is willing to accept this "as-is" subject to Rider #2, Paragraph 2.

### B. Arrange for Employee Parking after Normal Working Hours:

The Lessor will allow employee parking in/near the building after normal working hours.

## C. Accessibility to Official Government Vehicles:

The existing parking procedure meets the Government's requirements and the Government is willing to accept it "as-is" subject to Rider #2, Paragraph 2.

# D. Identification of Parking Areas:

Government reserved parking spaces shall be assigned and marked as "reserved." The existing identification meets the Government's requirements and the Government is willing to accept the indentification "as-is" subject to Rider #2, Paragraph 2.

# E. Inspection of Parking Areas:

The Government reserves the right at all times, to inspect the parking premises. The existing inspection procedures meet the Government's requirements and the Government is willing to accept the procedures "as-is" subject to Rider #2, Paragraph 2.

## F. Post Signs and Arrange for Towing of Unauthorized Vehicles: TENANT IMPROVEMENT

The existing-towing procedures meet the Government's requirements and the Government is willing to accept them "as-is" subject to Rider #2, Paragraph 2.

## G. ID System and Procedures for Authorized Parking: TENANT IMPROVEMENT

An ID system for authorized parking shall be provided by the Lessor, acceptable to the Government, for identification of vehicles and corresponding parking spaces (placard, decal, card key, etc.). The existing ID system and procedures meet the Government's requirements and the Government is willing to accept the procedures "as-is" subject to Rider #2, Paragraph 2.

# 9.25 CCTV MONITORING: CCTV SURVEILLANCE CAMERAS WITH TIME LAPSE VIDEO RECORDING (NOV 2005)

The Lessor shall permit twenty-four hour Closed Circuit Television (CCTV) coverage and recording, provided, operated, and maintained by the Government. The Government's Building Security Assessment of the building will determine the exact number of cameras and locations. Time-lapse video recordings (digital storage) are also required. The Government will centrally monitor the CCTV Surveillance. Government specifications are available from the Contracting Officer. The existing CCTV monitoring procedures under this paragraph meet the Government's requirements and the Government is willing to accept "as-is".

9.26 CCTV MONITORING: POST SIGNS ADVISING OF 24-HOUR VIDEO SURVEILLANCE (TENANT IMPROVEMENT) (NOV 2005)

When video surveillance is installed, warning signs advising of twenty-four hour surveillance shall be posted.

INITIALS:

LESSOR

GOV'T

SFO NO.06-031 09/07/06

46

#### 9.27 SHATTER-RESISTANT WINDOW PROTECTION REQUIREMENTS (NOV 2005) (BUILDING SHELL)

- A. The Lessor shall allow the installation, wet-glazed or mechanically attached, shatter-resistant material not less than 0.18 millimeters (7 mil) thick on all exterior windows in Government-occupied space. The Offeror shall provide a description of the shatter-resistant window system in the attached "Pre-Lease Building Security Plan" for evaluation by the Government. The existing window protection under this paragraph meets the Government's requirements and the Government is willing to accept the window protection "as-is"
- B. The Lessor shall provide certification from a licensed professional engineer that the window system conforms to a minimum glazing performance condition of "3B" for a high protection level and a low hazard level. Window systems shall be certified as prescribed by WINGARD 4.1 or later or WINLAC 4.3 software to have satisfied the specified performance condition using the test methods provided in the US General Services Administration Standard Test Method for Glazing and Window Systems Subject to Dynamic Overpressure Loadings or ASTM F1642-04 Standard Test Method for Glazing and Glazing Systems Subject to Airblast Loadings. The Government accepts the existing window system "as-is" and will not require certification of performance from the Lessor.

## SPECIAL REQUIREMENTS

#### 10.1 SPECIAL REQUIREMENTS:

# **BUILDING SHELL**

- During non-duty hours, the Lessor shall provide an electronic key card perimeter security system which covers all building entrances which shall be independently monitored 24 hours a day by a GSA-approved, class A commercial monitoring station, and provide a level of security which reasonably deters unauthorized entry to the leased space. In addition, a key card access security system allowing the government to control individual floor access from all of the elevators servicing the leased space is required.
- B. The Lessor shall, upon request of the Contracting Officer, shall take reasonable steps to attempt to deter loitering or disruptive acts in and around the space leased during duty hours.
- C. If requested, the Lessor must provide a detailed outline of the building standard security system.
- D. In cases of a building emergency, or where building security has been compromised or breached, the GSA Buildings Manager and the GSA Federal protective service must be notified immediately by the Lessor and/or the Lessor's agent.
- The owner shall provide a reasonable effort to integrate the building security system with any tenant specified security systems as identified below. The Lessor, at the Government's sole cost, shall make a reasonable effort to do this but shall have no obligation to make or allow any upgrades or significant alterations to the existing Building security system.

### SECURITY: ADDITIONAL REQUIREMENTS

## A. TENANT IMPROVEMENT INFORMATION

- 1. As part of the rental consideration, the Government must have the right and the ability to implement all security requirements as necessary in accordance with the June 28th, 1995, Vulnerability Assessment of Federal Facilities report of the U.S. Department of Justice, Federal Protective Service/Homeland Security Department requirements, Interagency Security Council recommendations, or as required to meet the agency's security requirements. The Government shall only be responsible for actual costs for improvements and shall be paid for through tenant improvement allowance or shall be paid for in a lump sum at the Government's sole option. Such improvements may include, but are not limited to the following:
  - The Government may integrate a Security Command Center, and a Security Guard Force with a presence on each Government occupied floor, to conduct access control procedures, video observation of Government space, Floor Patrols, etc.
  - The Government has the requirement for one secure parking space in the building and and designated for the Government's exclusive use. Such parking shall be enclosed (as described in Section 1.5 Unique Requirements) and secured with key card access, at the Lessor's sole cost, as acceptable to the contracting office.
  - The Government must have the right and the ability to fully control access to the Government occupied floors and Secure Parking space at all times. The Government must have the right and the ability to immediately "lock down" or prevent ingress or egress onto these floors and/or secured parking space in emergency situations, including during a security emergency as determined by the government, and the Lessor shall have no cause of action against the Government. Furthermore the Offeror must submit as part of it's offer certification in writing that such Government action will not cause the Offeror to be in breach of any existing lease, contract, or other agreement; or in the alternative, the Offeror must agree in writing to indemnify and hold harmless the Government against any loss, damage, claims, liability, or expense (including, but not limited to reasonable attorney's fees) related to a breach of lease, contractor or agreement by the Offeror resulting from the Government's action pursuant to it's rights under this section. Moreover, the Offeror agrees that upon award of the lease, the Offeror/Lessor will not

INITIALS: LESSOR &

enter into any subsequent lease, contract, or other agreement that conflicts with or in any way limits the Government rights under this section.

2. The Government reserves to require that all electrical, mechanical, and plumbing equipment be secured and alarmed. Such areas that may be identified will be paid for as a part of tenant's improvements unless otherwise required in this SFO.

## 3. Rooftop Security

As part of the rental consideration, the Government, with Landlord approval, such approval shall not be unreasonably withheld, conditioned or delayed, shall have roof rights to accommodate the Government's two (2) existing security and communications antennas or satellite dishes currently installed on the roof, and one (1) additional antenna or satellite dish. Installation of such additional equipment shall be coordinated with Lessor and installed in accordance with roof warranties. Any antennas or satellite dishes shall be installed in a manner to maintain aesthetic and structural integrity of the building and will be in accordance with Rider #2, Paragraph 11. In the event that the roof shall require maintenance, repair or replacement, the Lessor will advise the government prior to roof repairs. In no event shall the Lessor be responsible for personal property of the Government placed on the roof top pursuant to this paragraph.

INITIALS: LESSOR & COV'T

SFO NO.06-031 09/07/06

48